



Phone No. 24327671



E-mail: aeesrfti@gmail.com

**PRASAR BHARATI**  
(India's Public service Broadcaster)  
OFFICE OF THE ASSISTANT ENGINEER (ELECTRICAL)  
CIVIL CONSTRUCTION WING: ALL INDIA RADIO  
S.R.F.T.I. SUB-DIVISION-II: E.M.BYE PASS  
PANCHASHYAR: KOLKATA-94.

No. AE (E)/SRFTI-II/2018-19/11/ 452

Dated.15.03.2019

**NOTICE INVITING QUOTATION**

The Assistant Engineer (Electrical), CCW, AIR, SRFTI, Kolkata-94 invites sealed quotation for and on behalf of the President of India from the Manufacturer/Authorized Dealer/Distributor/Stockiest/Supplier, specialized agencies/firms working in the relevant field so that it will reach this office up to 3.00 P.M. on **25.03.2019** and will be opened on the same day at 3.30 P.M.

Name of work: MOEI ,Fans i/c street gate, flood lighting,RMO pump sets for ph-I & II at SRFTI, Kolkata for the year 2018-19.(SH:-wiring for computer pt.circuits, power point, and providing of electrical energy meter etc)

Sl.No	Description of item	Qty	Rate	Unit	Amount
	As per attached schedule.				

**Terms & Conditions:**

1. The rates quoted shall be net & inclusive of all duties, F.O.R. SRFTI E.M. Bye Pass, Panchashyar, Kolkata-94.
2. Rate shall be quoted in figures as well as in words also.
3. The time for completion of the works is 07 (Seven) Days.
4. No advance payment will be allowed.
5. The undersigned reserves right to cancel any or all the quotations without assigning any reason.
6. The quotations will be opened in presence of the quotationer or their authorized representatives who intend to be Present on the opening date.
7. Unsealed quotation will summarily be rejected.
8. Test certificate for hydraulic testing to be submitted by the agency.
9. The above NIQ is also available on web site [www.tenderhome.com](http://www.tenderhome.com) & [www.allindiaradio.gov.in](http://www.allindiaradio.gov.in)
10. The schedule of quantity will be issued by this office on request by the agency on producing of required documents with application.
11. The rates quoted shall be net and GST will not be paid extra as applicable on quoted rate. Hence the rate should be quoted with adding GST. GST registration certificate should be attached.

To  
M/S

*15.03.19..*  
ASSISTANT ENGINEER (ELECTRICAL)

Copy to: 1. The Executive Engineer (Electrical), CCW, AIR, Kolkata-95 for information pleases.  
2. Notice Board.

ASSISTANT ENGINEER (ELECTRICAL)

Schedule of work

Name Of Work:-MOEI ,Fans i/c street gate,flood lighting,RMO pump sets for ph-I & II at SRFTI,Kolkata for the year 2018-19.(SH:-wiring for computer pt.circuits,power point, and providing of electrical energy meter etc)

Sl.No	Description of item	Qty.	Rate	Unit	Amount
1	Providing & fixing (25 mm X 12 mm) pvc casing capping on surface complete etc as required.	110	Mtr	Mtr	
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit/pvc casing as required.				
a)	3 X 1.5 sq.mm	30	Mtr	Mtr	
b)	3 X 2.5 sq.mm	30	Mtr	Mtr	
c)	3 X 4 sq.mm	64	Mtr	Mtr	
3	Supplying and fixing of following piano type switch / socket on the existing switch box / cover including connection etc as required.				
a)	5/6 A switch	4	Nos	Nos	
b)	3 pin 5/6 A socket outlet	3	Nos	Nos	
c)	15/16 A switch	2	Nos	Nos	
d)	6 pin 15/16 A socket outlet	2	Nos	Nos	
4	Supplying and fixing of following size/modules pvc box alongwith modular base & cover plate for modular switches on surface etc as required.				
a)	3 Module	3	Nos	Nos	
b)	12 Module	8	Nos	Nos	
5	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc as required.				
a)	5/6 A switch	31	Nos	Nos	

b)	3 pin 5/6 A socket outlet	31	Nos	Nos
c)	15/16 A switch	12	Nos	Nos
d)	6 pin 15/16 A socket outlet	12	Nos	Nos
e)	25 A Socket outlet	16	Nos	Nos
6	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required.			
a)	2 Module	16	Nos	Nos
7	Supplying and fixing of 230 mm x 125 mm x 3 mm thick phenolic laminated sheet cover on existing board etc as reqd.(Guest House Barth room)	16	Nos	Nos
8	SITC of electrical Energy meter i/c connection, inter connection etc as reqd.(HPL make single phase, 2 wire, 5-30A, 240V, Model-SPEM 01. or similar make) (For Staff Qtr.)	1	No	No
9	SITC of electrical Energy meter( L & T make 3 phase 4 wire 50-100A cat no.WM 301 BC 8 D10/ similar make) in the molded case thermoplastic pvc box of size 300 mm x 450 mm x 170 mm depth (Approx) with detachable cover with gasket (HPL make, Model-Mi 0301/ similar make) with 25 sq mm single core copper conductor FRLS insulated cable of 0.35 x 8 nos length and 100 A connectors( 8 Nos) for lead connection facility complete etc as reqd.( For shooting connection/Temporary connections in different locations inside campus)	1	Job	Job

*18/03/15*  
 Assiatant Engineer(Elect)