

	<p style="text-align: center;"> <b>प्रसार भारती : PRASAR BHARATI</b>  <b>[ भारत का लोक सेवा प्रसारक : INDIA's PUBLIC SERVICE BROADCASTER ]</b>  <b>Office of the Additional Director General(E)(SZ)</b>  <b>AIR &amp;TV Swami Sivananda Salai</b>  <b>CHENNAI-600005</b> </p>	
---	---	---

No: ADG(E)(SZ)/INST/AIR/IO-76/2022-23/P

Dated:02.12.2022.

### Enquiry

**Sub:- Providing and constructing Profile Sheet Shed for 25KVA DG set at 100W FM AIR, ALLAGADDA, DEVARAKONDA, SIRPUR, RAMAGUNDAM & BHAGALKOT – Reg:-**

This office is interested in the following works for which you are requested to furnish your quotation. The scope/description of the work is furnished here under.

Sl No	Description of work	Qty	Rate	Amount
1	<p>Providing and constructing sloping Profile Sheet roof Shed for 25 KVA Diesel Generator of size as per enclosed Drawing at 5 Nos of LPTV/All India Radio stations at 1) Allagadda(AP), 2) Devarakonda, 3) Sirpur, 4) Ramagundam(Telangana) &amp; 5) Bhagalkot(Karnataka) as per following:</p> <p>A) 12' width, 15' Long and height of 11.6' at the centre, sloping on both sides to 10' height at the end as shown in the enclosed Drawing.</p> <p>B) Sloping sides should be given support by matrix of 6 Nos of tubular channels of 3"x 1.5" size and 4 Nos of tubular channels 1.5" x 1.5" size. Tubular channels at the centre has to be joined with 6mm MS Plate fitted with 12mm MS Bolts, nuts &amp; washers.</p> <p>C) Vertical 4 supports through 3" dia pipe has to be provided at the corners.</p> <p>D) Half curved PVC Pipechannel has to be provided at edge of sloping side to drain out the rain water.</p>	5Jobs (1Each at 5 sites)		

	<p>E) Four Foundation Bolts at a length of 3 feet with suitable dia for each of Vertical supports shall be dig with 300mm x 300mm x 600mm and filled with 1 : 2 : 3 ratio of concrete mixture. The Poles shall be fitted properly with perfect 90 degree angle from the ground.</p> <p>F) Before fixing the top roof, the entire structure shall be painted with one coat of epoxy metal primer and two coats enamel paint properly.</p> <p>G) Corrugated colour Metal Roofing preferable sky blue colour (Similar to Everest) shall be provided with the 1090mm x 3050mm length with a cover width of 1006mm with thickness of 0.45mm(TCT) and strength as per GL SSOMPA as per AS:1397. The Colour metal roofing sheets shall be fitted with proper Clamp</p>			
			Sub Total	
			GST	
			Grand Total	

**Note: Firm has to quote for all subitems individually.**

General Terms and Conditions:

- The above work has to be carried out in the presence of I.O/Engineering Head of the station. The above work has to be carried out within 30 days from the date of issue of Work Order.
- Billing: Installation Officer, AIR, Allagadda, Devarakonda, Sirpur, Ramagundam, Bhagalkot.
- Terms of Payment: 100 % Payment on completion of work.
- The quotation should be sent in a sealed cover addressed to DDG(Sound Project), O/o ADG(E)(SZ), AIR & TV, Swami Sivananda Salai, CHENNAI-5, **so as to reach on or before 20.12.2022, 11.00 AM.**
- THE COVER SHOULD BE SUPERSCRIBED WITH THE FOLLOWING:
  - Work for which quotations are enclosed.
  - Reference to letter of enquiry.
  - Due date of opening quotation.
- The Quotations will be opened in this office at **11:30 hrs. on 20.12.2022** in the presence of tenderers or their agents such as they may choose to attend.
- QUOTATIONS NOT PROPERLY SUPERSCRIBED WILL NOT BE CONSIDERED.
- GUARANTEE / WARRANTY PERIOD: The Work shall be guaranteed for a period of 1 **Year** from the date of commissioning. Any failure in the work carried out, during the Guarantee period shall be repaired / replaced free of charge by the Contractor at the Site.
- Both your **PAN – Permanent Income Tax Account Number and GST Number** should be definitely indicated in your quotation.
- Taxes:** GST leviable and intended to be claimed from the purchaser should be distinctly shown along with prices quoted. Where this is not done no claim for GST will be admitted at any later stage and on any ground whatsoever.

11. The contractor shall make his own arrangement for storage of all equipment and materials brought to site from time to time and their safe custody at site till they are taken over by the indenter/his representative. The contractor shall make his own arrangement for providing accommodation for his workmen at site.
12. The contractor shall make his/her own arrangements for procuring necessary labor, skilled and unskilled. He should conform to all local government laws and regulations covering labor and their employment.
13. The contractor and his employees shall comply with the regulation in force for controlled entry into premises where work is being carried out
14. Contractor liable for damage caused during installation work and imperfections notice
15. The contractor shall indemnify and hold harmless the purchaser against all claims in respect of injury or life to any person howsoever arising out of the work in the course of such installation/work. The contractor shall discharge his entire obligation under the Indian Workmen Compensation Act in as far as it affects workmen in his employment.
16. **RIGHT OF ACCEPTANCE:** The Additional Director General (E) (SZ), AIR & TV reserves the right to reject the lowest tender or all the tenders without assigning any reasons whatsoever. Further, the undersigned reserves himself the right for decreasing the quantity of material tendered depending upon the actual requirements. The unit rate quoted on the tender shall be applicable for the quantity for which order is placed.
17. The Additional Director General (E) (SZ), AIR & TV, Chennai also reserves the right to place **Repeat Order** for 100% or less quantity for which the quotation has been originally invited/order placed.

  
Yours faithfully

**SANJEEV K.P**  
**Director(E)**

## DG Shed Drawing

