



**P R A S A R   B H A R A T I**  
(INDIA'S PUBLIC SERVICE BROADCASTER)  
**CIVIL CONSTRUCTION WING, ALL INDIA RADIO**  
MUMBAI-91

No. AEC-I/BOV/12(NIQ)/2023-24/206

Dated: 11.12.2023

**NOTICE INVITING QUOTATION**

Sealed item rate quotations are invited by The Assistant Engineer (Civil)-I, CCW, AIR, Borivali, Mumbai-91 from the eligible and approved contractors of C.P.W.D. and those on appropriate list of B.S.N.L./M.T.N.L., M.E.S., State P.W.D. of Maharashtra and railways as well as eligible working contractor of CCW AIR for the following work, upto **15.00 hrs.** On **15.12.2023** which shall be opened on the same day at **15.30 Hrs.**


Blank quotation duly signed by Assistant Engineer shall be issued to the agency on submission of application with definite proof of having executed civil work and GST registration no. and acknowledgement of upto date GSTR 1 returns. The blank quotation verified and issued by Assistant Engineer shall only be validated and accepted authority.

Name of work : Day to day maintenance of MSQ staff quarter building during the year 2023-24 from October 2023 of All India Radio, Borivali, Mumbai-91					
Sr. No	Description	Qty.	Unit	Rate	Amount
----- AS PER ATTACHED SHEET -----					
<b>TOTAL:</b>					

**CONDITIONS:**

1. The work shall be carried out as per CPWD Specifications, 2009 Vol. I & II with upto-date correction slips and as per direction of Engineer-in-charge;
2. Time limit for completion of work is 15 (fifteen) days
3. Quoted rates shall be inclusive of all taxes and levies payable under the respective states including GST, nothing extra will be paid on any account;
4. The agency shall visit the site of work before quoting, as no extra payment will be made on any account. Such as extra thickness of base course depths and all height of buildings etc.
5. All type of security measures / precautions of labour shall be responsibility of agency during execution of work. No extra payment will be made on any account.
6. If the work is prolonged beyond stipulated time the penalty shall be imposed @ week.
7. The agency will be responsible for any defect for a period of 12 (twelve) months after issuing completion certificate for the work by Engineer-in-charge & client department. If any defect found during the defect liability period, the agency shall rectify the same within 7 days after receiving the notice from Engineer-in-charge in any form failing which the defective work shall be got rectified / replaced completely at the risk & cost of the agency and no claim whatsoever shall be entertained in this regards. The agency may note that the recovery shall be made from any of the payments due with the department or will be under legal obligation to refund the cost incurred by department in rectification / replacement of the defective work come to the notice of Engineer-in-charge during defect liability period;
8. No advance payment shall be made;
9. Labour should be above 18 years of age.

**CONTRACTOR**

  
(M.G. Kurhe)  
**ASSISTANT ENGINEER (CIVIL)-I**  
**CCW AIR PB (IPSB) MUMBAI-91**

Copy to:

1. The Executive Engineer (Civil), Civil Construction Wing, All India Radio, Mumbai-20;
2. The Assistant Engineer Civil (P), CCW, AIR, Mumbai.
3. Notice Board
4. Contractors M/s. \_\_\_\_\_

## SCHEDULE OF WORK

State Maharashtra  
Branch Civil  
Name of Work : Day to day maintenance of MSQ staff quarter building during the year 2023-24 from October 2023 of All India Radio, Borivali, Mumbai-91  
Division Mumbai  
Sub-Division Mumbai-I

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (RS)	RATE (In Words)	AMOUNT(RS)
1	Providing and fixing IS : 12817 marked stainless steel butt hinges with stainless steel screws etc. complete :					
1.1	100X58X1.90 mm	6	each			SR
2	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete :					
2.1	200x10 mm	4	each			SR
3	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :					
3.1	125 mm	4	each			SR
4	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.					
4.1	Single rubber stopper	10	each			SR
5	Providing and fixing bright finished brass 100 mm mortice latch and lock, ISI marked, with six levers and a pair of anodised (anodic coating not less than grade AC 10 as per IS : 1868) aluminium lever handles of approved quality with necessary screws etc. complete.	2	each			SR
6	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.					
6.1	Bend 87.5°					
6.1.1	75 mm bend	2	each			SR
6.1.2	110 mm bend	2	each			SR



ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
7	Providing services of labour for day to day maintenance of VBS/MSQ Complex including hire and running charges of necessary tools and plant, screws/nails, safety gadgets to work at height, insurance of labour etc. as required (A)Skilled labour like carpenter / plumber / mason / painter I class etc.	15	each			MR
8	Providing services of labour for day to day maintenance of VBS/MSQ Complex including hire and running charges of necessary tools and plant, screws/nails, safety gadgets to work at height, insurance of labour etc. as required (B)Unskilled labour ( Helper / Beldar / Coolie )	15	each			MR
9	Providing and applying Asian smart care damp proof paint or equivalent on wall and terrace in two coats including preaparing base by scrapping , cleaning and filling cracks with crack sealent of approved make( crack seal to be paid extra) at any height of high rise building including providing working platform (zulla) etc complete as per direction of Engineer-in-charge.	85	sqm			MR
10	Providing and fixing unplasticised rigied PVC soil, waste and vent pipes etc. complete. 150 mm diameter.	3	metre			MR
11	Providing and fixing panelled door shutter made of anodised aluminium hollow pipe section of size 70 x22 mm for vertical style and horizontal ( top/bottom/lock) rails including panelling of 4 mm thick aluminium composite panel sheet and cost of rubber/neoprene gasket required etc complete as per direction of Engineer-in-charge.	1.45	sqm			MR
12	Repairing 15 mm C.P.brass bibcock/pillar tap/ stop cock by replacing brass spindle of standard size and approved quality etc complete as per direction of Engineer-in charge.	5	each			MR
13	Providing and fixing PVC net of 20 mm aperture of approved quality to protect pigeon entry to window/balcony grill including pvc locking thread/ ms binding wire etc complete as per direction Engineer-in-Charge.	24	sqm			MR
14	Cleaning and desilting of Manhole chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in-charge.	3	each			MR

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
15	Providing and fixing 600x450 mm mirror of superior glass of approved quality with hard board/ pvc board ground etc complete as per direction of Engineer-in-Charge.	2	each			
	Total					

MR

Junior Engineer

Assistant Engineer

Executive Engineer