



**P R A S A R   B H A R A T I**  
(INDIA'S PUBLIC SERVICE BROADCASTER)  
**CIVIL CONSTRUCTION WING, ALL INDIA RADIO**  
MUMBAI-91

No. AEC-I/BOV/12(NIQ)/2023-24/

Dated: 24.11.2023

**NOTICE INVITING QUOTATION**


Sealed item rate quotations are invited by The Assistant Engineer (Civil)-I, CCW, AIR, Borivali, Mumbai-91 from the eligible and approved contractors of C.P.W.D. and those on appropriate list of B.S.N.L./M.T.N.L., M.E.S., State P.W.D. of Maharashtra and railways as well as eligible working contractor of CCW AIR for the following work, upto **15.00 hrs.** On **01.12.2023** which shall be opened on the same day at **15.30 Hrs.**

Blank quotation duly signed by Assistant Engineer shall be issued to the agency on submission of application with definite proof of having executed civil work and GST registration no. and acknowledgement of upto date GSTR 1 returns. The blank quotation verified and issued by Assistant Engineer shall only be validated and accepted authority.

Name of work : Cleaning of RCC Sump well, Overhead RCC water storage tank , terrace PVC tank of type D,C, B staff qtr bldg of All India Radio, Nasik.					
Sr. No	Description	Qty.	Unit	Rate	Amount
----- AS PER ATTACHED SHEET -----					
<b>TOTAL:</b>					

**CONDITIONS:**

28. The work shall be carried out as per CPWD Specifications, 2009 Vol. I & II with upto-date correction slips and as per direction of Engineer-in-charge;
29. Time limit for completion of work is 15 (fifteen) days
30. Quoted rates shall be inclusive of all taxes and levies payable under the respective states including GST, nothing extra will be paid on any account;
31. The agency shall visit the site of work before quoting, as no extra payment will be made on any account. Such as extra thickness of base course depths and all height of buildings etc.
32. All type of security measures / precautions of labour shall be responsibility of agency during execution of work. No extra payment will be made on any account.
33. If the work is prolonged beyond stipulated time the penalty shall be imposed @ week.
34. The agency will be responsible for any defect for a period of 12 (twelve) months after issuing completion certificate for the work by Engineer-in-charge & client department. If any defect found during the defect liability period, the agency shall rectify the same within 7 days after receiving the notice from Engineer-in-charge in any form failing which the defective work shall be got rectified / replaced completely at the risk & cost of the agency and no claim whatsoever shall be entertained in this regards. The agency may note that the recovery shall be made from any of the payments due with the department or will be under legal obligation to refund the cost incurred by department in rectification / replacement of the defective work come to the notice of Engineer-in-charge during defect liability period;
35. No advance payment shall be made;
36. Labour should be above 18 years of age.

  
(M.G. Kurhe)

**ASSISTANT ENGINEER (CIVIL)-I**  
**CCW AIR PB (IPSB) MUMBAI-91**

**CONTRACTOR**

Copy to:

13. The Executive Engineer (Civil), Civil Construction Wing, All India Radio, Mumbai-20;
14. The Assistant Engineer Civil (P), CCW, AIR, Mumbai.
15. Notice Board
16. Contractors M/s. \_\_\_\_\_



# SCHEDULE OF WORK

State  
Branch  
Name of Work : Cleaning of RCC Sump well, Overhead RCC water storage tank , terrace PVC tank of type D,C, B staff qtr bldg of All India Radio, Nasik.

Division  
Sub-Division

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)	SR
1	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre) (if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account)	8501	litre				SR
2	Cleaning of under ground sump, Over Head R.C.C. Tank ( independent staging) including disposal of slit and rubbish, all as per direction of Engineer-in-Charge. The cleaning shall consist following operations:- Tank shall be emptied of water by pumping & bottom shall be cleaned of silt and other deposits. Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge.	172.5	sqm				SR
	Total						

Junior Engineer

Assistant Engineer

Executive Engineer

*(M.G. KURHE)*  
ASSISTANT ENGINEER (CIVIL)-I  
CGW, ALL INDIA RADIO MUMBAI-91