



PRASAR BHARATI
India's Public Service Broadcaster
Office of the Assistant Engineer(E)
Civil Construction Wing: All India Radio
Siliguri-734008

Office Phone No:0353 2590329, e-mail: aeccwslg@yahoo.com

No. AE(E)/SLG/NIQ/(14)/2020/ 168

Date:- 29.01.2021

NOTICE INVITING QUOTATION
NO:01/AE(E)/SLG/2020

Sealed quotations are invited from approved & eligible contractors of appropriate list of CPWD/M.E.S/BSNL/MTNL/RAILWAYS/STATE PWD & other building department of State Govt. if there is no State P.W.D, on behalf of the President of India on item rate basis for the items noted below, so as to reach to the undersigned on or before 04.02.2021 by 3.00 PM. The quotations shall be opened on the same day at 3.30PM. The quotations should be super scribed as ``Quotation`` for... *, due on ...04.02.2021

* **Name of work:** NAME OF WORK : - Replacement of damaged Service connection UG cable for Pump Room for AIR Staff Qtrs. Hakimpara, (Near Mitra Nursing Home), Siliguri

Sl.No.	DESCRIPTION OF ITEMS	QTY	UNIT	RATE.	AMOUNT
- AS PER SHEET ATTACHED -					

Terms and Conditions:-

1. The quotation must accompany with Enlishment , work experience Certificate, GST registration, EPF & EST registration Certificate and electrical works licence etc.
2. The work should be carried out as per CPWD Specification.
3. I.T. will be applicable as per existing rule.
4. Time allowed for completion of the work will be 15(fifteen) days only after issue of award letter.

Copy to: 1) The Superintending Engineer(Elect) CCW,AIR,Kolkata.
2) TheExecutive Engineer (Elect) CCW,AIR,Patna.
3) The Executive Engineer (Elect) CPWD, Siliguri.
4) The Assistant Accounts Officer(Elect),CCW,AIR,Patna.
5) The Executive Engineer (Civil), CCW,AIR,Siliguri.
6) The Electrical Contractors Association of Eastern India,
81/2/7, Phears Lane, Kolkata-700012.
7) Notice Board.
8) Prasar Bharati website.

(Signature)
29/1/2021

ASSISTANT ENGINEER (ELECT)
CCW:AIR:SILIGURI

Name of Work :- Replacement of damaged service connection UG cable for pump room for AIR staff qtr, Hakimpara,(Near Mitra Nursing Home), Siliguri.

Sl. No.	Description of items	QTY.	Rate	Unit	Amount
1	Dismantlig of existing 4x16 sqmm (45 mtrs. approx) underground service connection cable from overhead pole to pump room including dismantling of GI pipe in CC floor etc. as required.	1 Job.		Job	
2	Re-laying of exisisting 50 mm dia GI pipe under the CC floor inclding cutting and making the same / on surface on wall or along with the RCC pole of overhead lines etc. as required as follows :-				
	a) Under the CC floor.	22 mtrs.		Mtr.	
	b) On surface along with pole with 2 nos. MS clamps.	3 mtrs.		Mtr.	
3	Providing and fixing of following GI accessories (med) for existing GI protection pipe for underground service connection cable as required.				
	a) 50mm dia GI socket.	7 nos.		Each.	
	b) 50mm dia GI bend	3 nos.		Each.	
	c) 50mm dia, 300mm GI nipple.	1 no.		Each.	
4	Renovation of existing metering board by dismantling of the damaged (rusted) cubical panel board and installing the energy meter on a wooden board including providing and fixing of wooden board of size 500mmx500mmx20mm thick and 4 nos 32 Amp Cut out with rewirable fuses etc. as required.	1 Job.		Job	
5	Supplying of 4X16 Sq.mm XLPE insulated & PVC sheathed armoured U.G. aluminium conductor power cable of 1.1 KV grade conforming to IS:7908(Part-I)1998 with upto date ammendments including laying the same in the following manners complete as required :-				
	(a) Direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required.	21 mtrs.		Mtr.	
	(b) In the existing RCC/ HUME/ METAL pipe as required.	5 mtrs.		Mtr.	
	(c) in open duct as required.	8 mtrs.		Mtr.	
6	Renovation of existing switch board by replacing the following accessories along with PVC insulated FRLS copper wire of size 1.0 sqmm including connection, testing etc as required :-				
	(a) Selector switch - 01 no.				
	(b) 0-30A Ammeter (Essma make) - 01 no.				
	(c) 5Amp ISI marked piano type switch - 3 nos.				
	(d) Piano type ISI marked indicator lamp - 3 nos.				
	(e) Piano type ISI marked fuses - 3 nos.				
		1 Job.		Job	

Sl. No.	Description of items	QTY.	Rate	Unit	Amount
6	Renovation of existing switch board by replacing the following accessories along with PVC insulated FRLS copper wire of size 1.0 sqmm including connection, testing etc as required :- (a) Selector switch - 01 no. (b) 0-30A Ammeter (Essma make) - 01 no. (c) 5Amp ISI marked piano type switch - 3 nos. (d) Piano type ISI marked indicator lamp - 3 nos. (e) Piano type ISI marked fuses - 3 nos.	1 Job.		Job	
7	Supplying and making outdoor end termination with cast resin compound including aluminium lugs and other jointing materials for following size of PVC insulated and PVCsheathed / XLPE aluminium conductor cable of 1.1KV grade as required. (a) 4X16 Sqmm.	1 Job.		Job	


 Assistant Engineer (Elect)
 CCW: AIR: Siliguri