



P R A S A R B H A R A T I
(INDIA'S PUBLIC SERVICE BROADCASTER)
CIVIL CONSTRUCTION WING, ALL INDIA RADIO
MUMBAI-91

No. AEC-I/BOV/12(NIQ)/2023-24/ 205

Dated: 11.12.2023

NOTICE INVITING QUOTATION

Sealed item rate quotations are invited by The Assistant Engineer (Civil)-I, CCW, AIR, Borivali, Mumbai-91 from the eligible and approved contractors of C.P.W.D. and those on appropriate list of B.S.N.L./M.T.N.L., M.E.S., State P.W.D. of Maharashtra and railways as well as eligible working contractor of CCW AIR for the following work, upto **15.00 hrs.** On **15.12.2023** which shall be opened on the same day at **15.30 Hrs.**

Blank quotation duly signed by Assistant Engineer shall be issued to the agency on submission of application with definite proof of having executed civil work and GST registration no. and acknowledgement of upto date GSTR 1 returns. The blank quotation verified and issued by Assistant Engineer shall only be validated and accepted authority.


Name of work : Repairing of compound wall with half brick work for broken portion including plastering on both side at east face upto BSNL compound wall at VBS,AIR,Borivali,Mumbai-91
SH: Structural repair plaster to the RCC post /column of compound wall

Sr. No	Description	Qty.	Unit	Rate	Amount
----- AS PER ATTACHED SHEET -----					
TOTAL:					

CONDITIONS:

1. The work shall be carried out as per CPWD Specifications, 2009 Vol. I & II with upto-date correction slips and as per direction of Engineer-in-charge;
2. Time limit for completion of work is 15 (fifteen) days
3. Quoted rates shall be inclusive of all taxes and levies payable under the respective states including GST, nothing extra will be paid on any account;
4. The agency shall visit the site of work before quoting, as no extra payment will be made on any account. Such as extra thickness of base course depths and all height of buildings etc.
5. All type of security measures / precautions of labour shall be responsibility of agency during execution of work. No extra payment will be made on any account.
6. If the work is prolonged beyond stipulated time the penalty shall be imposed @ week.
7. The agency will be responsible for any defect for a period of 12 (twelve) months after issuing completion certificate for the work by Engineer-in-charge & client department. If any defect found during the defect liability period, the agency shall rectify the same within 7 days after receiving the notice from Engineer-in-charge in any form failing which the defective work shall be got rectified / replaced completely at the risk & cost of the agency and no claim whatsoever shall be entertained in this regards. The agency may note that the recovery shall be made from any of the payments due with the department or will be under legal obligation to refund the cost incurred by department in rectification / replacement of the defective work come to the notice of Engineer-in-charge during defect liability period;
8. No advance payment shall be made;
9. Labour should be above 18 years of age.

CONTRACTOR


(M.G. Kurhe)
ASSISTANT ENGINEER (CIVIL)-I
CCW AIR PB (IPSB) MUMBAI-91

Copy to:

1. The Executive Engineer (Civil), Civil Construction Wing, All India Radio, Mumbai-20;
2. The Assistant Engineer Civil (P), CCW, AIR, Mumbai.
3. Notice Board
4. Contractors M/s. _____

SCHEDULE OF WORK

State Maharashtra

Branch Civil

Name of Work :

Repairing of compound wall with half brick work for broken portion including plastering on both side at east face upto BSNL compound wall at
VBS,AIR,Borivali,Mumbai-91
Division Mumbai
Sub-Division Mumbai-I

SH: Structural repair plaster to the RCC post /column of compoun wall

ITEM No	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	NEW TECHNOLOGIES AND MATERIALS					
1.1	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect.					
1.1.1	SBR Polymer (@10% of cement weight) modified cementitious bond coat @ 2.2 kg cement per sqm of surface area mixed with specified proportion of approved polymer	42	sqm			
1.2	Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded coarse sand with polymer minimum 2% by wt. of cement used) as per specifications and directions of Engineer-in-charge. Note: Measurement and payment: The pre-measurement of thickness shall be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and/or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N/Sqmm2).					
1.2.1	50 mm average thickness in 3 layers.	42	sqm			
	Sub-Total					
	Total					

SR

SR