



PRASAR BHARATI
(INDIA'S PUBLIC SERVICE BROADCASTER)
O/o ADDITIONAL DIRECTOR GENERAL (E) (WZ)
ALL INDIA RADIO & DOORDARSHAN
P.B.ROAD, WORLI, MUMBAI-30.



No. ADG (E) (WZ)/AIRM/4T AC/2024-25/

Dated. 18/07/2024

Extension-1

SUBJECT: - INVITATION OF BUDGETARY QUOTE FOR THE PROCUREMENT OF 16 Nos. OF FLOOR MOUNTING TOWER TYPE 4 TON SPLIT AIR CONDITIONER AT GWALIOR (MP), UJJAIN (MP.), CHHATARPUR (MP), MUMBAI(MH.), BAMBOLIM(GOA), PANAJI (GOA), REWA(MP) AND JALGAON(MH).

1. The budgetary quote Form of the upcoming tender is enclosed herewith to offer comments, (if any) by prospective bidders/firms with budgetary quote.
2. Bidders/firms may please submit the above details/their quote on or before due date by e-mail to : airmaintenancewiz@gmail.com at following address.


Sh. N.W.JOSHI
Assistant Director(E),
O/o Additional Director General (E-WZ)
Akashvani Maintenance Section,
Akashvani & Doordarshan, 1st floor, A.O.A building,
Doordarshan Complex, Worli, Mumbai – 400030
Mobile No.: 9869254803

e-mail id: airmaintenancewiz@gmail.com

Due Date to offer Comments: 22.07.2024.

Enclosed:

1. Budgetary Quotation form of the upcoming tender is enclosed herewith.


(N.W.JOSHI)
निरीक्षक (ए) / N.W. JOSHI
For Add. Dir. Gen. (E-WZ)
O/o Additional Director General (Engg. WZ)
आकाशवाणी एवं दूरदर्शन, Mumbai
AIR & DOORDARSHAN, WORLI, MUMBAI-30



PRASAR BHARATI
(INDIA'S PUBLIC SERVICE BROADCASTER)
O/o ADDITIONAL DIRECTOR GENERAL (E) (WZ)
ALL INDIA RADIO & DOORDARSHAN
P.B.ROAD, WORLI, MUMBAI-30.



No. ADG (E) (WZ)/AIRM/4T AC/2024-25/

Dated. 18/07/2024

Budgetary Quotation Form

Extension-1

SUBJECT: - INVITATION OF BUDGETARY QUOTE FOR THE PROCUREMENT OF 16 NOS. OF FLOOR MOUNTING TOWER TYPE, 4 TON SPLIT AIR CONDITIONER AT GWALIOR (MP), UJJAIN (MP.), CHHATTARPUR (MP), MUMBAI(MH.), BAMBOLIM(GOA), PANAJI (GOA), REWA(MP) AND JALGAON(MH).

Last date of receipt of budgetary quotation in this office: 22.07.2024

Please read carefully the terms and conditions given the enquiry quotation form.

S No	Description	Qty	Rates	Amount
1)	Floor mounting type, 4 Ton Split Air Conditioner along with (1). Stand for both ODU & IDU. (2). 10Mtr. Refrigerant copper pipe & Power cable as per IS . (3). Drain pipe.	16 Nos.		
2)	Installation, Testing and Commissioning of the Floor mounting type, 4 Ton Split Air Conditioner at each site.	16 Places		
	Total			
	GST @			
	Grand Total			

Note:

1. Consignee: Engineering Head, Akashvani site Gwalior(02Nos.), Ujjain(01No.), Chhattarpur(02 Nos), Worli(Mumbai)- 03 Nos., Panaji(02 Nos.), Bambolim(Goa) – 01 No., Rewa(03 Nos.) and Jalgaon(02 Nos.).
2. Time of execution as per permission of engineer in charge at Akashvani site Gwalior, Ujjain, Chhattarpur, Worli(Mumbai), Panaji, Bambolim(Goa), Rewa and Jalgaon.
3. The bidder must be experienced in same kind of scope.
4. Specifications of the item to be procured are attached with this form, filling the budgetary quote specifications should be considered extensively.
5. Supply has to be done as per the terms and condition in upcoming tender documents.
6. Quantity of Material & Scope may increase or decrease as per actual requirement/ constraints at site.
7. Validity: 120 days
8. Declaration: We declare that all the conditions as given in the quotation form have been read by us.

Name (in capital)

(Seal & Signature of the Bidder)

Air Conditioner, Floor mounting Tower Type, 4 Ton split AC, conforming to IS 1391 (Part 2) Product Details

Availability of BIS/ISI Mark Certification for Split AC Floor type	: Yes
Make in India	: Yes
Nominal Marketing capacity as per BEE Star Rating Label (hint: 1 Ton = 3000 Kcal/Hr, Tolerance +/- 10%)	:4 T
Rated voltage (in Volts) Tolerance Value for Rated Voltage As per IS 1391 (Part 2)	: 415 V, 3 Phase, 50 Hz, AC
Classification by function Cooling	: Only Cooling and dehumidification
AC Machine warranty (in Year)	:1 Year
Warranty on compressor	:5 Year

MATERIAL

Material of Evaporator	Copper
Material of Condenser	Copper

GENERAL FEATURE

Additional Features	Indoor Temperature Indicator, Dust Filter, Sleep mode
Availability of type test report from Govt Lab/ NABL accredited lab / ILAC accredited lab to prove conformity of the specification	Yes, as per IS 1391 (Part 2)

SCOPE OF INSTALLATION AND COMMISSIONING FOR FLOOR STANDING TOWER TYPE SPLIT AC

(1) Mounting/Fitting of indoor and outdoor units at the respective locations.

(2) Laying of refrigerant piping and connecting with indoor and outdoor units after drilling hole/holes in the wall (all type of walls), if required.

(3) Charging & Checking Refrigerant gas in the unit.

(4) Suitable electric wiring between indoor units and switches up to 10 meters in length.

(5) Refrigerant pipe of 10-meter length.

(6) Providing & Fixing Stand for ODU & IDU, Drain pipe.

(7) Testing for satisfactory working without any abnormal noise as well as leakage test of entire system.

