

No. EE(E)/M/2(40)/2024-25/236

Dated: 27.09.2024

NOTICE INVITING e-QUOTATION

The Executive Engineer (Elect), Civil Construction Wing, All India Radio, Chennai-04 on behalf of President of India invites item rate quotation from the approved and eligible Contractors of CPWD and those of appropriate list of M.E.S, BSNL Railway, Department of Post and State Government of Kerala dealing with buildings for the following work:

Name of work:	Replacement of outdoor CT-PT meter unit and TOD meter including earthing at AIR Devikulam
NIQ No:	03/EE(E)/CCW/AIR/CH/2024-25/ Dated. 29.04.2024
Estimated Cost:	Rs. 2,37,764/-
Period of completion:	Two (2) Months
e-tender processing fee	Nil
Last date for submission of bid	08.10.2024 up to 2.00 pm
Date of opening of Bids	08.10.2024 at 2.30 pm

The blank quotation duly signed by Executive Engineer(E) shall be issued to agency on submission of application and submit to this office on or before the last date for submission of bids. Bids received late or received without the documents specified below will be summarily rejected.

List of documents to be submitted along with the quotation

- 1.Enlistment order of the Contractor and Electrical license.
- 2.The certificate of registration of GST.(The agencies who are not registered with department for GST shall be liable for rejection of tender.)
- 3.The successful bidder shall submit the acknowledgement of GST returns for Aug 2024 within a week's time of opening date of quotation.

The bid forms and other details can be obtained from the web site

<https://prasarbharati.eproc.in>

Terms and conditions

1. The work should be completed as per CPWD specifications with upto date correction slips and as per the direction of Engineer-in-charge
2. No T&P will be issued departmentally.
3. The Quotations received without sealed cover and incomplete shape shall be summarily rejected.
4. The rates should be Net & inclusive of GST and levies.
5. The rates should be valid for one month from the date of opening.
6. No advance payment shall be made.
7. The work shall be completed within two months.


EXECUTIVE ENGINEER(ELECT.)
CCW,AIR,CHENNAI

Copy to:

1. The Director (Engg.), Akashvani, Devikulam for information.
2. The Assistant Engineer (E), CCW, AIR, Calicut information please.
3. Web updates pbns@gmail.com for publishing in AIR web site.
4. The Assistant Engineer(E)(P), CCW, AIR, Kochi.
5. Notice board.



EXECUTIVE ENGINEER(ELECT.)
CCW,AIR,CHENNAI

ABSTRACT OF COST

Name of work : Replacement of outdoor CT-PT meter unit and TOD meter including earthing at AIR Devikulam

Sl. No	Description of item	Quantity		Rate	Unit	Amount
1	Supplying, installing, testing and commissioning of out door type combined CT-PT unit, 3 phase 4 wire system, oil cooled, having 3 Nos resin cast CTs of 5/5A current ratio, 10 VA burden, accuracy class 0.2s and one No. PT of 11KV/110V votage ratio, burden 25 VA, accuracy class 0.2 in suitable container as per KSEBL specifications (BIS), installed on the existing 2 pole structure including connections from CT-PT unit to TOD meter by means of 12 core x 2.5 sq.mm copper wire etc.in corodination with the local KSEB authorities as required.(Make: M/s. Indus or Similar reputed brand coforming to BIS's specifications)	1	No		Each	
2	Supplying, installing, testing and commissioning of Device Language Messge Specification (DLMS) type electronic trivector TOD meter for 3 phase 4 wire system having accuracy class 0.2s compatible to IS 15959 CAT-C1 along with 3nos suitable size CTs & test terminal block installed in the prefixed place (Metering Kiosk) near the existing 2 pole structure including connections etc. in coordination with the local KSEB authorities.(Make: M/s. L&T)	1	No		Each	
3	Supplying and making cable end termination with brass compression gland and copper lugs suitable for 12 core x 2.5 sq.mm copper cable complete as required.	2	sets		set	
4	Service charges for testing and calibration of CT-PT meters and TOD meter at KSEB's TMR Division office and getting the test certificate including transportation charges, statutory testing charges, liaisoning charges etc complete as reured.	1	Job		Job	
5	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. along with charcoal/ coke and salt as required.	1	sets		Set	

6	Providing and laying earth connection from earth electrode with 4.00 mm dia copper wire in 15 mm dia G.I. pipe from earth electrode including connection with copper thimble excavation and re-filling as required.	8	Mtr		Meter	
7	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	4	Mtr		Meter	
8	Dismantling, removing and storing in AIR store of existing faulty outdoor CT-PT unit , TOD meter and connection cables etc. from the two pole structure including disconnection etc complete as required.	1	Job		Job	
	Total Amount					


 27/9/24
 EXECUTIVE ENGINEER (ELECT)