

No. EE(E)/M/2(36)/2024-25/

Dated: 10.10.2024

**NOTICE INVITING e-QUOTATION**

The Executive Engineer (Elect), Civil Construction Wing, All India Radio, Chennai-04 on behalf of President of India invites item rate quotation from the approved and eligible Contractors of CPWD and those of appropriate list of M.E.S, BSNL Railway, Department of Post and State Government of Kerala dealing with buildings for the following work:

Name of work:	<b>Replacement of faulty Incoming Cable for Pump Room at Akashvani, Kochi.</b>	
NIQ No:	<b>05/EE(E)/CCW/AIR/CH/2024-25/</b>	<b>Dated. 10.10.2024</b>
Estimated Cost:	<b>Rs. 1,42,224/-</b>	
Period of completion:	<b>Two (2) Months</b>	
e-tender processing fee	<b>Nil</b>	
Last date for submission of bid	<b>18.10.2024 up to 2.00 pm</b>	
Date of opening of Bids	<b>18.10.2024 at 2.30 pm</b>	

The blank quotation duly signed by Executive Engineer(E) shall be issued to agency on submission of application and submit to this office on or before the last date for submission of bids. Bids received late or received without the documents specified below will be summarily rejected.

**List of documents to be submitted along with the quotation**

- 1.Enlistment order of the Contractor and Electrical license.
- 2.The certificate of registration of GST.(The agencies who are not registered with department for GST shall be liable for rejection of tender.)
- 3.The successful bidder shall submit the acknowledgement of GST returns for Aug 2024 within a week's time of opening date of quotation.

The bid forms and other details can be obtained from the web site

**<https://prasarbharati.eproc.in>**

**Terms and conditions**

1. The work should be completed as per CPWD specifications with upto date correction slips and as per the direction of Engineer-in-charge
2. No T&P will be issued departmentally.
3. The Quotations received without sealed cover and incomplete shape shall be summarily rejected.
4. The rates should be Net & inclusive of GST and levies.
5. The rates should be valid for one month from the date of opening.
6. No advance payment shall be made.
7. The work shall be completed within two months.

  
EXECUTIVE ENGINEER(ELECT.)  
CCW,AIR,CHENNAI

**Copy to:**

1. The DDG), Shri.Babu Mathew, AE, Akashvani, Kochi for information.
2. The Assistant Engineer (E), CCW, AIR, Calicut information please.
3. Web updates pbns@gmail.com for publishing in AIR web site.
4. The Assistant Engineer(E)(P), CCW, AIR, Kochi.
5. Notice board.

  
EXECUTIVE ENGINEER(ELECT.)  
CCW,AIR,CHENNAI



PRASAR BHARATI  
(INDIA'S PUBLIC SERVICE BROADCASTER)  
EXECUTIVE ENGINEER (ELECTRICAL)  
ELECTRICAL WING:AKASHVANI: CHENNAI -04.

**Tender number: NIQ.No.05/EE/E/CCW/AIR/CHN/2024-25**

**Name of Work: Replacement of faulty Incoming Cable for Pump Room at Akashvani, Kochi.**

NAME OF THE CONTRACTOR						
Sl.No	DESCRIPTION OF ITEM	QUANTITY		RATE (Rs)	UNIT	AMOUNT (Rs)
1	Supplying and laying DWC HDPE pipe of size 63 mm X 51 mm ISI marked along with couplers and other accessories, if required, conforming to IS 16205, complete with cutting, jointing, fitting etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	100.00	Mtrs		Mtr	-
2	Supplying and laying of one number of 4 X 16 sq. mm size, aluminium conductor, PVC insulated and PVC sheathed / XLPE, armoured power cable of 1.1 KV grade with ISI mark, in the existing DWC HDPE/GI pipe as required.	115.00	Mtrs		Mtr	-
3	Supplying and laying of one number of 4 X 16 sq. mm size, aluminium conductor, PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade with ISI mark, in the existing masonry open duct/ for connection as required.	6.00	Mtrs		Mtr	-
4	Supplying and making end termination with brass compression gland and aluminium lugs for 4 X 16 sq. mm size for PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	2.00	Sets		Set	-
5	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	121.00	Mtrs		Mtr	-

6	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	5.00	Nos		Each	-
7	Providing, laying and fixing of 50 mm dia GI pipe (medium class) in gound complete with fittings including concrete road cutting, trenching (75 cm deep) and refilling the trench, making good the road cutting using 1:2:4 cement concrete etc. as require	15.00	Mtrs		Mtr	-
8	Spray painting of existing metallic panel board(outside and inside) in installed position with one coat of epoxy primer and two coats of epoxy top coat of approved brand and shade including cleaning the surface with with emery paper, wiping with thinner, replacing damaged rubber gasket, nuts, bolts if any, complete as required.	1.00	Job		Job	-
<b>TOTAL</b>						-

  
 10/10/24  
 EXECUTIVE ENGINEER(E)