## प्रसार भारती (भारत का लोक सेवा प्रसारक) आकाशवाणी:पासीघाट



# PRASAR BHARATI INDIA'S PUBLIC SERVICE BROADCASTER AKASHVANI:PASIGHAT

 $\hbox{E-MAIL ID: } pasighat a ir 66@gmail.com/engg.a ir. pasighat@gmail.com/pasighat@prasarbharati.gov. in the pasighat and the pasighat and the pasighat and the pasighat are pasighat are pasighat are pasighat are pasighat and the pasighat are pasighat are pasighat and the pasighat are pasighat are pasighat are pasighat and the pasighat are pasighat are pasighat are pasighat and the pasighat are pasig$ 

### NOTICE INVITING QUOTATION

No.PSG-1(2)/2024-25/E (FM-BOLENG) / 1622

Dated:08.11.2024

Subject: Quotation for 30 mtrs height guy mast repairing / maintenance works at 100 W FM Transmitter Akashvani Boleng (Arunachal Pradesh)

Dear Sir,

This office is interested in the undermentioned works as per the specification given below:-

Your quotaiton is invited as per the terms sand conditions given below on reverse

Sl. no.	Description of Works/Items	Quantity			
1	Newly construction of 03 Nos.guyanchore C.C. foundation for replacement of damaged existing guy anchor C.C foundation (size $3' \times 3' \times 3'$ ) cement ratio 1:2:2 including supply of required materials.				
2	Replacement of 09 Nos. existing old/damaged Mast guy ropes and same size new guy rope fixing at the same position properly, all ropes are equally proper tightening from mast body with guy anchor				
3	Painting of 30 mtrs height mast as per office specification (including supply of required painting materials etc.).				
4	Supply and construction of 02 Nos. G.I. plate earthing (size 600mm x 600mm x 6mm and strip size 25mm x 6mm thickness). Work will be done as per drawing.				
5	Dismantling of existing unstable TV Antenna and RF Cable from the top portion of the existing mast.				
6	Supply and fixing of one copper make 3ft long lightening arrestor set including supply of 10 sq mm x 35 mtr long copper wire.				
7	Supply of required materials:-				
a)	10mm thickness steel rope ISI standard - 260 mtr				
b)	Bull-dog grip for 10 mm thickness steel rope - 60 Nos.	-			
c)	Thimble for 10 mm thickness steel rope - 09 Nos.				
d)	Anchor bolt as per required size (500 kg capacity) - 27 Nos.	1 job			
e)	Strain screw as per required size(2 feet long) - 09 Nos.				
f)	Guy Anchor rod (3' long 25 mm dia) - 03 Nos.				
		4.10			

#### **Terms and conditions:**

- 1 The rates should be indicate in figure as well as words.
- The quotation should be sent to the undersigned by name along with the descriptions of works/items, name of supplier/contractor and specification etc. as per requirement of this office. The terms and conditions, validity period etc. should seperately be mentioned in cover envelop or ignore whichever is not necessary. The same must be sealed and containing quoted prices, GST etc. to be furnised in the quotation or in the quotation form enclosed herewith so as to reach within 12.00 hours on or before 25.11.2024 in sealed cover, quotations by giving the following details.
- a Works/ Stores/ Items for which quotations are enclosed. (b) Reference of enquiry letter.
- b Date of opening quotations. (d) Name and address of the Tenderer. (e) Details of quotations should be submitted in the enclosed form or Firm's quotation form.
- The quotations will be opened in the office of the undersigned at 3.00 pm on 25.11.2024 in the presence of the tenderer or their agents who may choose to attend.
- The quotations as submitted should remain open for acceptance for a period of 6 months from the date of opening.
- 5 Every care has to be taken for the safety of the operating/carrying the above mentioned works/stores/Items at the risk of Supplier/Contractor.
- 6 The firm quoting a lowest rate for entire work should be considered as Successful Bidder(L1).
- 7 The quotation should be fulfilled with the requisite particulars for GST implication.
- 8 The DD (E)/HoO, Akashvani Pasighat reserves the right to reject any or all the quotations without assigning any reasons.
- 9 The quility work should be guaranted for 1 (one) year after completion.
- This office reserves the right to terminate the contract if the workmanship is found unsatisfactory. The decission of Head of Engineering in the matter will be final and undisputable. Income tax will be deducted from firms bill at the prescribed rates and the prescribed certificate for TDS will be issued.
- 11 Communication /Postal Address:- The Deputy Director(E), Akashvani, Pasighat, East Siang District, Arunachal Pradesh- 791102

#### Copy to:

- i) CPP portal (e-publishing)
- ii) <u>webupdates.pbns@gmail.com with a request to publish the Notice inviting quotation on prasarbharati.gov.in</u>
- iii) <u>prasarbharatisupport@c1india.com with a request to publish the Notice inviting quotations on prasarbharati.eproc.in</u>
- iv) The Cluster head/HOO, Akashvani, Itanagar-791111
- iv) Akashvani Pasighat office Notice Board.

(Modi Prasad) DDE/HoE

Akashvani Pasighat.

Deputy Director (E)

All India Radio Pasighat

# Prasar Bharati (India's Public Service Broadcaster) Akashvani, Pasighat-791102

QUOTATION FORM

Enquiry No.PSG-1(2)/2024-25/E (FM-BOLENG)//622

Dated: 08.11.2024

Subject: Quotation for 30 mtrs height guy mast repairing / maintenance works at 100 W FM Transmitter Akashvani Boleng (Arunachal Pradesh)

Opening date of quotation at Akashvani, Pasighat on 25-11-2024.

1				IGST	Amount
	Newly construction of 03 Nos.guyanchore C.C. foundation for replacement of damaged existing guy anchor C.C foundation (size 3' x 3' x 3') cement ratio 1:2:2 including supply of required materials.	1 Job			
2	Replacement of 09 Nos. existing old/damaged Mast guy ropes and same size new guy rope fixing at the same position properly, all ropes are equally proper tightening from mast body with guy anchor	1 Job	,		
3	Painting of 30 mtrs height mast as per office specification (including supply of required painting materials etc.).	1 Job			
4	Supply and construction of 02 Nos. G.I. plate earthing (size $600 \text{mm} \times 600 \text{mm} \times 6 \text{mm}$ and strip size $25 \text{mm} \times 6 \text{mm}$ thickness). Work will be done as per drawing.	1 Job			
5	Dismantling of existing unstable TV Antenna and RF Cable from the top portion of the existing mast.	1 Job			
6	Supply and fixing of one copper make 3ft long lightening arrestor set including supply of 10 sq mm x 35 mtr long copper wire.	1 Job			
7	Supply of required materials:-				
a)	10mm thickness steel rope ISI standard - 260 mtr		1		
b)	Bull-dog grip for 10 mm thickness steel rope - 60 Nos.				
c)	Thimble for 10 mm thickness steel rope - 09 Nos.				
d)	Anchor bolt as per required size (500 kg capacity) - 27 Nos.	1 job			
e)	Strain screw as per required size(2 feet long) - 09 Nos.				
f)	Guy Anchor rod (3' long 25 mm dia) - 03 Nos.				

- 1. Period of validity of tender: 6 (six) months
- 2. Rate may be quoted including GST/IGST.
- 3. Firm Quotation No.

Signature & Date

Full Address with Rubber Stamp of the Firm

Note:

Information as stated in the quotation should be clearly specified, otherwise the quotation is liable to be rejected.