



प्रसार भारती
Prasar Bharati
भारत का लोक सेवा प्रसारक
India's Public Service Broadcaster
कार्यालय: अपर महानिदेशक (अभि.) (उत्तरी क्षेत्र)
Office of the Additional Director General (E) (NZ)
आकाशवाणी एवं दूरदर्शन
Akashwani & Doordarshan
आठवां तल, सूचना भवन, सी.जी.ओ. कॉम्प्लेक्स, नई दिल्ली 110003
8th floor, Soochna Bhawan, CGO Complex, New Delhi-110003



सत्यम् शिवम् सुन्दरम्

Haldwani/2V/3/2023-24/Instt/(Misc.Works)

Dated: 22.03.2024

Subject: Misc. Works at AIR Haldwani.

1. The budgetary quotation with drawing of the upcoming tender is enclosed herewith to offer comments, if any by prospective bidders/firms.
2. Bidders/firms are requested to provide information about content in respect of works along with budgetary quote.
3. Bidders/firms may please submit the above detail on or before due date by e-mail to bcbelwal@prasarbharati.gov.in or at following Address.

Assistant Engineer
Room No. 899-B,
O/o ADG(E-NZ)
Akashwani & Doordarshan,
8th floor, CGO Complex,
Soochna Bhawan, New Delhi-110003
Mob No.: 09868539587
Email id: bcbelwal@prasarbharati.gov.in

Budgetary Quotation for: Misc. Works at AIR Haldwani.

Due Date to offer Comments: 29.03.2024

Enclosed:

1. Budgetary Quotation form of the upcoming tender is enclosed herewith to offer comments, if any by prospective bidders/firms.

(B. C Belwal)
Assistant Engineer
For Additional Director General (E) (NZ)



Haldwani/2V/3/2023-24/Instt/(Misc. Works)

Date:

Budgetary Quotation Form**Project:** Installation of 10 kW FM Transmitter at AIR Haldwani.**Subject :** Misc. Works at AIR Haldwani.

Please read carefully the terms and conditions given the enquiry quotation form.

S.No.	Description	Qty	Rates	Amount
1.	Earth work for the leveling of the surface area around the 100 meter S.S. steel tower & within the premises and along the boundary wall, the work shall be executed as per following. a) Clearing and cleaning the area by removing the wild growth, bushes, and grass from the area around 275 sqm. b) Excavation of heap of soil and spreading of the soil on the pits all around.- approx. 10 M3. c) Providing, filling and leveling the 84 M3 (cubic meter) soil. The leveling is to be done at average ground level. The average depth of the filling is approximately 1' deep. To complete the work the necessary heavy machinery such as Truck/ Dumpers, tractor with trolley, tools and labour has to be arranged by bidder. NOTE: The site is within the premises of Tehsil and state treasury and this is a heavy crowded place at day time. So, this work must be executed at late night hours only.	1 job		
2.	Replacement of old and damaged wooden doors as per follow: a) Dismantling of existing doors of size 6' x 7½' from their places. b) Providing an fixing wooden door made up of 40 mm flush door and 1 mm mica from both side. c) Fixing of all necessary hardware such as sliding bolts, tower bolts, hinges, door closer and door stopper mechanism on both leafs of doors.	2 No		
3.	Provision of LT Transformer enclosure for security purpose:- The enclosure should be fabricated as per below:- a) Providing, fabricating, grouting and fixing of LT Transformer enclosure of size 9'x12'x6' (H). the enclosure should be made up of 40x40x5mm angle iron for vertical pillars (6no) and horizontal top rail, and 1"x1" M.S. Jali as covering material with 2" flat M.S.patti for horizontal middle support, it include priming and painting 2 coat each of reputed make. b) Making C.C. flooring inside this enclosure by cleaning the area and digging the earth surface 6" deep and providing & filling PCC in ratio 1:4:8 after excavating the soil. After the PCC providing & filling the CC mixture in ratio 1:2:4 and finishing the surface with queering for at least 5 days.	1 Job		
4.	Repairing of the damaged plastering work on walls by scavenging and cleaning the affected area in patches and providing and applying the cement sand mixture in ratio 1:4 with neat finish and cleaning the working area after finishing the work. Total area is in patches and approx- 42 sqmtr in all.	1Job		
5.	Supply and applying of exterior wall paint the scope of work is as per below:- a) Removing of old & damaged wall paint by scrubbing the old painting flakes/ scaling at affected area with the help of sand paper b) Providing & applying two coat of wall exterior primer on the complete outer wall surface of building.	520 Sqmtr		

1183977/2024/AIR-Co. Section - Zonal Office (NZ)	c) Providing & applying two coat of weather proof exterior paint of top coat make -sikkens astral, the bidder after the primer work on the complete outer wall. surface of building .			34
6.	Supply of wooden table for read over room (ROR) made up of 3''x3'' wooden (sal/sheshum) batten for frame and legs and 19mm HDMR board and 4mm vinear of approved shade on the top.	1no		
7.	Supply of wooden pedestal for the use as stands for speakers at read over room (ROR) and Studio made up of 19mm HDMR board and 4mm vinear of approved shade on the	4No		
	Total			
	GST @			
	Grand Total			

Note:

- Time of execution as per permission of Engineer Incharge at AIR Haldwani.
 - The bidder must be experienced in same kind of scope & shall submit documentary evidence with offer. The Completion certificate is to be attached, issued by any Govt. Agency only.
 - Execution of scope has to be completed without break in service at AIR Haldwani.
 - Before submitting the offer tenderer must visit site and with prior permission of the site in-charge and submit confirmation of site visit. Technical details will be provided by In-charge of Site/I.O.
 - The firm has to produce a list all such labour along with the address proof which are to be employed office on signing contract. The firm shall issue the identity cards to all such persons to facilitate the entry in at AIR Haldwani.
 - Inspection will be carried out preferably in presence of Authorized representative of ADG (NZ), AIR & DD, 8th floor, Sochna Bhawan, CGO Complex, New Delhi-110003.
 - Any damage or misplace in equipment will have to be provided by the firm during execution.
- 1) Quantity of Material & Scope may increase or decrease as per actual requirement/constraints at site.
 - 2) Please read carefully the terms and conditions given in this quotation form.
 - a) GST No: b) PAN No.....
 - 3) **Delivery at:** Installation of 10kW FM Transmitter at AIR Haldwani.
 - 4) **Consignee:** Installation officer, AIR Haldwani.
 - 5) **Completion Period:** Execution of scope is to be complete within two months from the date of order.
 - 6) **Validity:** 120days
 - 7) **Payment terms:**
 - 95% Payment on completion/execution of scope in good condition at site.
 - Balance payment of 05% will be paid after guarantee/warranty period of one year. However payment can be released against FDR/Account Payee Demand Draft/Banker's Cheque of equivalent amount in favour of CE (NZ), AIR & DD, New Delhi valid for guarantee period at least.
 - 8) **Performance Security:**
 - The firm/contractor should submit performance security deposit in the form of FDR from a schedule commercial bank valid for one year in favour of Chief Engineer (NZ), AIR & DD, New Delhi.
 - The Performance Security Deposit shall be 05% of cost of the order/contract value.
 - 9) **Declaration:** We declare that all the conditions as given in the quotation form have been read by us.

Name (in capital) _____
Seal: (Signature of the Bidder)