

प्रसार भारती Prasar Bharati

भारत का लोक सेवा प्रसारक

India's Public Service Broadcaster कार्यालयः अपर महानिदेशक (अभि.) (उतरी क्षेत्र)

Office of the Additional Director General (E) (NZ)

आकाशवाणी एवं दूरदर्शन

Akashwani & Doordarshan

आठवां तल, सूचना भवन, सी.जी.ओ. कॉम्प्लेक्स, नई दिल्ली 110003 8th floor, Soochna Bhawan, CGO Complex, New Delhi-110003



सत्यम् ज्ञिवम् स्न्दरम्

Dated: 31.01.2025

Rampur/2V/3/2024-25/Instt./(Misc. Electrical Works)

Subject: Laying of 185 Sq mm 31/2 core and 95 Sq mm 31/2 core armoured Al. Conductor cable & other related works at Akashvani Rampur (Uttar Pradesh).

- 1. The budgetary quotation of the upcoming bid is enclosed herewith to offer comments, if any by prospective bidders/firms.
- Bidders/firms are requested to provide information about content in respect of scope along 2. with budgetary quote.
- 3. Bidders/firms may please submit the above detail on or before due date by e-mail to bcbelwal@prasarbharati.gov.in or at following address.

B. C Belwal

Assistant Director (Engg.)

Room No. 899-B,

O/o ADG (E)(NZ)

Akashvani & Doordarshan,

8th floor, CGO Complex.

Soochna Bhawan, New Delhi-110003

Mob No.: 09868539587

e-mail id: bcbelwal@prasarbharati.gov.in

Budgetary Quotation for: Laying of 185 Sq mm 31/2 core and 95 Sq mm 31/2 core armoured Al.

Conductor cable & other related works at Akashvani Rampur (Uttar

Pradesh).

Due Date to budgetary offers & comments: 10.02.2025

Enclosed:

Budgetary Quotation form of the upcoming bid is enclosed herewith to offer comments, if any by 1. prospective bidders/firms.

> Assistant Director (Engg.) For Add. Director General (NZ)

भुवन चन्द्र बेलवाल सहायक निदेशक (अभि.)



प्रसार भारती Prasar Bharati भारत का लोक सेवा प्रसारक

India's Public Service Broadcaster कार्यालयः अपर महानिदेशक (अभि॰) (उत्तरी क्षेत्र) Office of the Additional Director General (E) (NZ) आकाशवाणी एवं दूरदर्शन



Date: 31.01.2025

Akashvani & Doordarshan आठवां तल, सूचना भवन, सी.जी.ओ. कॉम्प्लेक्स, नई दिल्ली 110003 8th floor, Soochna Bhawan, CGO Complex, New Delhi-110003

Rampur/2V/3/2024-25/Instt./(Misc. Electrical Works)

Budgetary Quotation Form

Please read carefully the terms and conditions given the enquiry quotation form.

Project: Setting up of 10kW (1+1) FM Transmitter at Akashvani Rampur (Uttar Pradesh).

Subject: Laying of 185 Sq mm 3½ core and 95 Sq mm 3½ core armoured Al. Conductor cable & other related works at

Akashvani Rampur (Uttar Pradesh).

Las	t date of receipt of budgetary quotation in this office: 10.02.2025 upto 12:	00Hrs		
S.No.	Description	Qty.	Rates	Amount
1.	Laying of 185 Sq mm and 95 sqmm 3½ core armoured Al. Conductor G.I. strip armoured PVC sheathed of (150Mtr length)from state electricity board energy meter to LT Panel inside the LT Panel room and 95 sqmm cable 50 mtr two length to and from LT panel to DG set respectively (100mtr) as per follow:-			
i.	Digging of trenches of size 450 mm x 600 mm total length (a) 118(88+30)mtr for 185 sq mm and starting from state electricity board energy meter to LT Panel inside the LT Panel room and to and (b) 28mtr for 95 Sq mm from LT panel to DG set respectively: by digging the Path which includes cement Concrete flooring and road and removing the Malba from the trench. Laying one layer of 4" thick Sand for cable in the trench.	118+28= 140 Meter		
ii.	Providing & grouting of 2 Nos. of 3"dia G.I. Pipes of different length on the Cement concrete Flooring and along the vertical walls. Total length of both pipes is 27 mtr.	27 Meter		
iii.	Providing, grouting & fixing 2 Nos. of 4" dia G.I. Pipes along the MS stand of main MCCB at energy meter. Total length of both pipes is 14 mtr.	14 Meter		
iv.	 Unwinding roll of 185 sq. mm 3½ core aluminium cable (total length of 150 mtr in two pieces) and 95 sq mm 3½core(two length 50 mtr each): from their cable drum and laying the cable through the Trenches & through the G.I. Pipes as laid down above in Para (i), (ii), (iii) Respectively. Providing the aluminium armoured cable jointer heat shrinkable kit and jointing the two length of 185 sq mm 3½ core armoured Al cable. Making the 3mtr loop on both sides of 185Sq mm Al cable. Filling the 4" thick layer of sand over the cables in the trenches Providing and fixing common bricks over the sand bed in entire trench. Filling the soil over the trench up to the ground level & leveling the area. 	1 Job		
٧.	Reconstructing the CC Flooring and repairing the area with Cement concrete and stone aggregate mixer 1:2:4 and finishing the surface, Complete in all respect.	1 Job		
vi.	Providing and Making cable connection with Aluminum lugs of two length each of both cables of 185 Sq. mm and 95 Sq. mm of Phase and Neurtal and earthings at the both end of the cable and make ready for connection at both end.	1 Job		
vii.	Providing & fixing of LT Cable route marker made up of $2\frac{1}{2}$ " dia signage with 10mm x 2' long Ms rod.	25 Nos.		
2.	Repairing of existing trenches:- The repairing of the trenches is to be carried out as per below. a) Removing of the damaged wooden cover of the trenches (144' long and 10" wide in pieces) from their places and removing out from the campus. b) cleaning of the trenches. c) Repairing of trench surface by filling the holes by plastering work. d) Removing the damaged portions of the GI angle frame by providing and fabricating same size angle iron frame (35mmx35mmx4mm). e) Providing and fixing wooden trench cover with 38mm plywood & mica in whole length of 144Rft& 10" wide in pieces of convenient size.	144 R.ft.		
3.	Closing of the existing trenches by brick masonary work & plastering & providing & fixing the vitrified flooring on top of this work total area 12' long and 10" wide.	1 Job		
4.	Replacement of old and damaged electrical wiring of the transmitter hall, LT room, UPS rooms, Corridor and technical area as per following;- a) Dismantling of old and damaged electrical wiring and all electrical points from their places. b) Marking for rerouting of the electrical wiring as per site requirement. c) Providing of the copper cable and electrical switch, socket, electrical switch board, fan regulators, ceiling covers, PVC flexible pipe, PVC casing caping, insulating tapes as per below:- Size of Copper cable Single Core, electrical switch, socket, electrical switch board, fan regulators, ceiling covers, PVC flexible pipe, PVC casing caping,	1 Job		

	nsulating tapes:-
	i. 4 Sq mm Single core:- 05 Roll (100mtr each)
	ii. 2.5 Sq mm Single core:- 10 Roll (100mtr each)
	iii. 1.5 Sq mm Single core:- 04 Roll (100mtr each)
	iv. 15 Amp Modular Switch -12Nos.
	v. 06/10 Amp Modular Switch – 36Nos.
	vi. 15 Amp Modular Socket – 12Nos.
	vii. 06/10 Amp Modular Socket – 15Nos.
	viii. 12M Grid & 12M Cover Switch board – 06Nos.
	ix. 8M Grid & 8M Cover Board - 12Nos.
	x. 4M Grid & 4M Cover Board – 10Nos.
	xi. 2M Grid & 2M Cover Board – 08Nos.
	xii. 12M Grid & 12M Cover board – 06Nos.
	xiii. Modular Fan regulator – 06Nos.
	xiv. Ceiling covers assorted Sizes -15 No
	xv. PVC Flexible pipe 1" and 2" - 05 Roll each
	xvi. PVC casing caping 1" and 2" - 10 Roll each
	xvii. PVC Insulating tapes - 02 Dozen
	xviii. MCB Box 18 way and 12way – 01 No. each
	xix. 65 Amp 4pole MCB – 02 Nos.
	xx. 32Amp 4Pole MCB- 03 Nos.
	xxi. 20Amp and 10 Amp single pole MCB – 16 Nos. each
	xxii. 20Amp Double Pole MCB – 08 Nos. each
	xxiii. 15Amp Switch & Socket combined – 07 Nos.
	d) Making the electrical circuit in consultation with site in-charge/I.O
	according to the site requirement.
	e) Fixing of the PVC casing caping and PVC flexible pipes as per required
	circuits.
	f) Fixing of the different switch board with different switch ,socket etc, MCB
	boards with all required circuit breaker MCB,
	g) Afterword laying & Dragging the copper cables through PVC casing
	caping, PVC flexible cable and existing MS conduits and connections of
	all electrical points.
	h) Proper earthing circuit should be insured for the complete wiring.
	i) Testing of all electrical point functioning.
	Fotal
	GST@
	Grand Total
NT - 4	Static Total

Note:

- > Time of execution as per permission of Engineer In-charge at Akashvani Rampur.
- The Tenderer must be experienced in same kind of scope& shall submit documentary evidence with offer. The Completion certificate is to be attached.
- \succ Execution of scope has to be completed without break in service at Akashvani Rampur.
- > Before submitting the offer tenderer must visit site and with prior permission of the site in-charge and submit confirmation of site visit. Technical details will be provided by In-charge of Site/I.O.
- The firm has to produce a list all such labour along with the address proof which are to be Employed Office on signing contract. The firm shall issue the identity cards to all such persons to facilitate the entry in at Akashvani Rampur.
- Inspection will be carried out preferably in presence of Authorized representative of ADG (NZ), Akashvani & Doordarshan, 8th floor, Soochna Bhawan, CGO Complex, New Delhi-110003
- \succ Any damage or misplace in equipment will have to be provided by the firm during execution.
- 1. Quantity of Material & Scope may increase or decrease as per actual requirement/constraints at site.
- $\textbf{2.} \quad \text{Please read carefully the terms and conditions given in this Quotation Form.} \\$
- a) GST No:b) PAN No......
- 3. **Delivery at:** Setting up of 10kW (1+1) FM Transmitter at Akashvani Rampur (Uttar Pradesh).
- 4. Consignee: Installation officer, Akashvani Rampur (Uttar Pradesh).
- **5. Completion Period:** Supply of material & completion of scope in good condition within 60days from the date of order.
- **6. Validity:** 120days
- 7. Payment terms:
 - > 97% Payment on completion/execution of scope in good condition at site.
 - ➤ Balance payment of 03% will be paid after guarantee/warranty period of one year. However payment can be released against FDR/Account Payee Demand Draft/Banker's Cheque of equivalent amount in favour of Chief Engineer (NZ), Akashvani & Doordarshan New Delhi valid for guarantee period at least.

8. Performance Security:

- a. The firm/contractor should submit performance security deposit in the form of FDR from a schedule commercial bank valid for one year in favour of Chief Engineer (NZ), Akashvani & Doordarshan New Delhi.
- b. The Performance Security Deposit shall be 03% of cost of the order/agreement value.
- c. For release of security deposit/performance security, the firm will submit his claim along with a certificate from the ultimate consignee that equipment supplied/SITC executed against this order has performed satisfactorily during its warranty/guarantee period and department have not suffered any loss/inconvenience on this account.
- 9. **Declaration:** We declare that all the conditions as given in the Quotation form have been read by us.

Name (in capital)_		
(Seal & Sign	ature of th	e Tenderer