प्रसारभारती / PRASAR BHARATI

(भारतकालोकसेवाप्रसारक/INDIA'S PUBLIC SERVICE BROADCASTER)
अपरमहानिदेशककाकार्यालय(अभि.) (द.क्षे..) / O/o. ADDL. DIRECTOR GENERAL (E)(SZ)
आकाशवाणीएवंदूरदर्शन / AKASHVANI& DOORDARSHAN
स्वामीशिवानंदासालै, चेन्नई/ SWAMY SIVANANDA SALAI, CHENNAI — 600 005.

e-mail:adgszpurchase@prasarbharati.gov.in

No. J-11022/12/2025-PURCHASE-ADG(E)-(SZ)

Date: 1.8.2025

Amendment II

Sub: DSETC of Self Supporting 75 m high Latticed Steel Tower for Akashvani Vellore-reg

Ref: 1. Tender No. J-11022/12/2025-PURCHASE-ADG(E)-(SZ) dated 11.6.2025

2. Amendment I dt 2/7/25

Sir,

With reference to the above, the following Amendments may be noted.

S1. No.	Existing	Amended
1	Appendix D: Section III: SCHEDULE OF REQUIREMENTS/ MATERIALS (UN-PRICED) FOR 75 M SELF SUPPORTING LATTICE STEEL TOWER; (I) Supply: Sl.No.7 Description: Supply of Lightning Arrester materials/arrangements including earthing materials for separate earthing (2 Nos.earthing) along with copper strip of size 50 mm × 2 mm from top of the tower to the ground with lug etc. complete as required. (II) Works: Sl. No. 10 Description: Installation of Tower Lightning Arrester and earthing work (2 Nos. earthing) along with laying of Copper strip of size 50 mm × 2 mm from top of the tower to the ground with lugs etc. complete as required.	Appendix D: Section III: SCHEDULE OF REQUIREMENTS/ MATERIALS (UN-PRICED) FOR 75 M SELF SUPPORTING LATTICE STEEL TOWER; (I) Supply: Sl.No.7 Description: Supply of Lightning Arrester materials/arrangements including earthing materials for separate earthing (2 Nos.earthing) along with copper strip of size 50 mm × 3 mm from top of the tower to the ground with lug etc. complete as required. (II) Works: Sl. No. 10 Description: Installation of Tower Lightning Arrester and earthing work (2 Nos. earthing) along with laying of Copper strip of size 50 mm × 3 mm from top of the tower to the ground with lugs etc. complete as required.



2 Price bid:- Supply of material: Sl.No.7 Description:

Supply of Lightning Arrester materials/arrangements including earthing materials for separate earthing (2 Nos.earthing) along with copper strip of size 50 mm × 2 mm from top of the tower to the ground with lug etc. complete as required.

Works: Sl. No. 10 Description:
Installation of Tower Lightning
Arrester and earthing work (2 Nos.
earthing) along with laying of Copper
strip of size 50 mm × 2 mm from top
of the tower to the ground with lugs
etc. complete as required.

Price bid:- Supply of material: Sl.No.7 Description:

Supply of Lightning Arrester materials/arrangements including earthing materials for separate earthing (2 Nos.earthing) along with copper strip of size 50 mm × 3 mm from top of the tower to the ground with lug etc. complete as required.

Works: Sl. No. 10 Description:

Installation of Tower Lightning Arrester and earthing work (2 Nos. earthing) along with laying of Copper strip of size **50 mm** × **3 mm** from top of the tower to the ground with lugs etc. complete as required.

Bidders need to submit Compliance in the Technical bid and offer rates in the price bid as per the above amendments.

All other terms and conditions remains the same.

P.Padmavathi Director(E) For ADG(BO) (SZ)

