



प्रसार भारती
Prasar Bharati
भारत का लोक सेवा प्रसारक
India's Public Service Broadcaster
कार्यालय: अपर महानिदेशक (अभि.) (उत्तरी क्षेत्र)
Office of the Additional Director General (E) (NZ)
आकाशवाणी एवं दूरदर्शन



Akashvani & Doordarshan
आठवां तल, सूचना भवन, सी.जी.ओ. कॉम्प्लेक्स, नई दिल्ली 110003
8th floor, Soochna Bhawan, CGO Complex, New Delhi-110003

सत्यम् शिवम् सुन्दरम्

AIR-Co/Gorakhpur/2V/3/2025-26/Instt./(PVC Flooring, painting & polishing of studios)

Dated:18.08.2025

Subject: Providing, Laying, Fixing of 4.0 mm thick PVC flooring (Roll Type) including dismantling of old PVC flooring and painting, polishing, POP, gypsum cornice & anti-termite treatment of Talk Studio, Control room, Playback Studio & Corridor at Akashvani Gorakhpur (UP).

1. The budgetary quotation of the upcoming bid is enclosed herewith to offer comments, if any by prospective bidders/firms.
2. Bidders/firms are requested to provide information about content in respect of scope along with budgetary quote.
3. Bidders/firms may please submit the above detail on or before due date by e-mail to rksrivastav@prasarbharati.gov.in or at following address.

R.K Srivastava
Assistant Director (Engg.)
Room No. 899-C,
O/o ADG (E)(NZ)
Akashvani & Doordarshan,
8th floor, CGO Complex,
Soochna Bhawan, New Delhi-110003
Mobile No.: 9873364977
e-mail id: rksrivastav@prasarbharati.gov.in

Budgetary Quotation for: Providing, Laying, Fixing of 4.0 mm thick PVC flooring (Roll Type) including dismantling of old PVC flooring and Painting, Polishing, POP, gypsum cornice & anti-termite treatment of Talk Studio, Control room, Playback Studio & Corridor at Akashvani Gorakhpur (UP).

Due Date to offer Comments: 22.08.2025

Enclosed:

1. Budgetary Quotation form of the upcoming bid is enclosed herewith to offer comments, if any by prospective bidders/firms.

**Assistant Director (Engg.)
For Add. Director General (NZ)**

रवीन्द्र कुमार श्रीवास्तव / Ravinder Kumar Srivastav
सहा. निदेशक (अभि.) / Asstt. Director (Engg)



AIR-Co/Gorakhpur/2V/3/2025-26/Instt./(PVC Flooring, painting & polishing of studios)

Date: 18.08.2025

Budgetary Quotation Form

Project: Refurbishing of studios under the component face-lift of DD/AIR Channels under project mode at Akashvani Gorakhpur (UP).
Subject: Providing, Laying, Fixing of 4.0 mm thick PVC flooring (Roll Type) including dismantling of old PVC flooring and Painting, Polishing, POP, gypsum cornice & anti-termite treatment of Talk Studio, Control room, Playback Studio & Corridor at Akashvani Gorakhpur (UP).

Last date of receipt of budgetary quotation in this office: 22.08.2025 upto 12:00Hrs.
Please read carefully the terms and conditions given the enquiry quotation form.

| S.No. | Description | Qty | Rates | Amount |
|-------|---|----------------|-------|--------|
| 1. | Dismantling, Providing, Laying and Fixing of 4.0mm thick acoustic vinyl flooring (Roll Type) in Talk Studio, Control room, Playback Studio & Corridor area at Akashvani Gorakhpur (UP), using IS standard adhesive suitable for bonding after cleaning and making the uneven surface to even suitable for the said scope. Description of scope as per measurement taken at site: a. Dismantling & making rolls of old fixed PVC vinyl flooring, stacking of dismantled PVC vinyl flooring debris material from the outside of the office premises. b. Cleaning, repairing and leveling of floor with POP mixed white cement to make the surface homogenous smooth. Masonry repair of floor at damaged position with cement, coarse sand, aggregate etc. c. Providing and fixing of new 4.0mm acoustic vinyl flooring of reputed make. d. Adequate and fully skilled labour shall be provided to complete the scope aesthetically and on time. e. Cushioning effect must be maintained to minimize the surface noise. f. Floor must be easy to clean and having low maintenance. g. After laying and fixing of PVC vinyl flooring the floor must be resistant against commonly used acid, alkalis, oils, grease and floor must be Slip retardant. | 250 Sq mtr | | |
| 2. | a) Providing and applying of wall finish, putty and POP on walls to make smooth finish for premium emulsion paint at Talk Studio, Control room, Playback Studio & Corridor area at Akashvani Gorakhpur (UP), after touching on corners etc. as required for water based luxury emulsion on these surfaces. Area shall be kept clean from dust etc. and all equipments in area shall be covered by PVC sheet properly for prevention from dust etc. b) Minor repairing of walls wherever required within the studio and other technical area by dismantling the old & damaged plastering work by providing and applying the cement sand mixture in ratio 1:4 and removing the debris from the working area. (if required) | 200 Sq.mtr | | |
| 3. | a) Providing & applying 2 coats of wall primer on gypsum false ceiling and walls etc. Talk Studio, Control room, Playback Studio & Corridor area, after touching on corners, joints and screw heads etc. as required at Akashvani Gorakhpur (UP). b) Providing & applying 2-3 coats of water based luxury emulsion on gypsum false ceiling and walls surface of above area. The area shall be kept clean from dust etc. and all equipments in area shall be covered by PVC sheet properly for prevention from dust etc. Talk Studio, Control room, Playback Studio & Corridor area at Akashvani Gorakhpur (UP). The water based luxury emulsion of reputed make and trade mark as Asian-Royale Emulsion, Dulux-Velvet Touch, Nerolac- Impressions Eco Clean/24 Carat, Berger-Silk or equivalent. | 625 Sq.mtr | | |
| 4. | Polish:- Wooden surface to be cleaned and wooden putty to be applied and after rubbing with appropriate sand paper to smooth the surface two or more coat of wooden polish to be applied in wainscot and doors of Talk Studio, Control room, Playback Studio & Corridor area at Akashvani Gorakhpur (UP). | 110 Sq. mtr | | |
| 5. | Providing & applying of 125mm x 125mm x 12mm POP/Gypsum cornice as per approved profile at all around false ceiling in Talk Studio, Control room, Playback Studio & Corridor area at Akashvani Gorakhpur (UP). | 203 R. mtr. | | |
| 6. | Anti-Termite treatment to ensure uniform distribution and proper penetration of treatment of treating solution at columns pits, wall trenches, top surface, and conduits, expansion joints junction walls & the floor etc as required in Talk Studio, Control room, Playback Studio & Corridor area at Akashvani Gorakhpur (UP). Complete in all respect in Studio premises at Akashvani Gorakhpur (UP). | 01 Job | | |
| | Important Note:- (Must read carefully) • Akashvani Gorakhpur is a running station of Akashvani and studios and other Technical area are available only during non working hours of station which may be in night time also. There will be limited working hours based on availability of concern studios. • Working hours shall be decided by engineering head. • The offered material & adhesives for bonding acoustic vinyl flooring should be of standard quality & reputed brand. • All Raw materials are required for completion of above is to be provided/supplied by the bidder. • All required material should be of reputed brand. • As the required scope is to be carried out in the running station the all job are required to be done in coordination with the station authorities. Total working hours per day shall be decided on the availability of the studios. • The bidder must be experienced in same kind of scope & shall submit documentary. • Above complete scope will be carried out in presence of authorized representative of this office. | | | |
| | Total | | | |
| | GST@ | | | |
| | Grand Total | | | |

Note:

- Details for acoustic vinyl flooring have been provided in bid for guidance of bidder. Bidder shall required visiting the site for understanding the clear requirement of scope before submitting the offer.
- Detailed BOQ and material specifications shall be submitted along with make, model (if applicable) of all the materials including technical leaflets of OEM as per the offered design.
- The supplier/contractor shall follow the best modern practice in the manufacture of high grade equipment not-withstanding any omission in that, the supplier/contractor shall in all respect design, engineer, manufacture, and supply the same within delivery period to the entire satisfaction of the organization.
- The scope of current bid/tender is providing, laying, fixing of 4.0 mm thick PVC flooring (Roll Type) and painting, polishing, POP, gypsum cornice & anti-termite treatment of Talk Studio, Control room, Playback Studio & Corridor at Akashvani Gorakhpur (UP).
- Tenderer shall require visiting the site for understanding the clear requirement of scope before submitting the offer.
- Detailed specifications shall be submitted as per scope.
- Experience details of similar scope executed during last seven years shall be submitted as per general terms and condition.
- Time of execution as per permission of engineer incharge at Akashvani Gorakhpur (UP).
- The bidder must be experienced in same kind of scope & shall submit documentary evidence with offer. The completion certificate is also to be attached issued by any Central and State Government agency, PSUs, Private organizations.
(In case of SITC/SETC and specialized scope, the contractor should also have sufficient experience and shall submit the experience certificate of satisfactory completion of at least three similar works, each of value not less than 40% of the estimated cost put to tender or two similar works, each of value not less than 60% of the estimated cost or one similar work of value not less than 80% of the estimated cost, all amounts rounded off to a convenient full figure, in the last 7 years ending on the last day of the month previous to the one in which the tenders are invited”).

- Execution of scope has to be completed without break in service at Akashvani Gorakhpur (UP).
 - Before submitting the offer tenderer must visit site and with prior permission of the site in-charge and submit confirmation of site visit. Technical details will be provided by In-charge of Site/I.O.
 - The firm has to produce a list all such labour along with the address proof which are to be employed office on signing contract. The firm shall issue the identity cards to all such persons to facilitate the entry in at Akashvani Gorakhpur (UP).
 - Inspection will be carried out preferably in presence of authorized representative of O/o ADG (NZ), AIR & DD, 8th floor, Soochna Bhawan, CGO Complex, New Delhi-110003.
 - Any damage or misplace in equipment will have to be provided by the firm during execution.
- 1) Quantity of Material & Scope may increase or decrease as per actual requirement/constraints at site.
- 2) Please read carefully the terms and conditions given in this quotation form.
- a) GST No: b) PAN No.....
- 3) **Delivery at:** Refurbishing of studios at Akashvani Gorakhpur (UP).
- 4) **Consignee:** Installation officer, Akashvani Gorakhpur (UP).
- 5) **Completion Period:** Execution/Completion of scope within 90days from the date of order.
- 6) **Validity:** 120days
- 7) **Payment terms:**
- 97% Payment on completion/execution of scope in good condition at site.
 - Balance payment of 03% will be paid after guarantee/warranty period of one year. However payment can be released against FDR/Account Payee Demand Draft/Banker's Cheque of equivalent amount in favour of Chief Engineer (NZ), Akashvani and Doordarshan, New Delhivalid for guarantee period at least.
- 8) **Performance Security:**
- The firm/supplier/contractor should submit performance security deposit in the form of FDR from a schedule commercial bank valid for one year in favour of Chief Engineer (NZ), Akashvani and Doordarshan, New Delhi.
 - The performance security deposit shall be 03% of cost of the order/contract value.
 - For release of security deposit/performance security, the firm will submit his claim along with a certificate from the ultimate consignee that equipment supplied/SITC executed against this order has performed satisfactorily during its warranty/guarantee period and department have not suffered any loss/inconvenience on this account.
- 9) **Declaration:** We declare that all the conditions as given in the quotation form have been read by us.

Name (in capital) _____
(Seal & Signature of the Bidder)