

PRASAR BHARATHI
(INDIA'S PUBLIC SERVICE BROADCASTER)
OFFICE OF THE ASSISTANT ENGINEER (CIVIL)
CIVIL CONSTRUCTION WING: ALL INDIA RADIO
14, TALUK OFFICE ROAD: SAIDAPET: CHENNAI-600 0015.
Email: aecccwchn@gmail.com

No.1/AEC-I/Chn/AIR/NIQ/2025-26/1

Dated: 06.10.2025.

NOTICE INVITING QUOTATION

Sealed Quotations are invited by the Assistant Engineer (Civil), CCW, AIR, Chennai-15 from the approved and eligible registered contractors of CPWD, MES, BSNL, Postal, Railways, and State PWD of Tamil Nadu for the following work

Sl.No.	Name of work	Qty.	Rate	Unit	Amount
1.	Providing GI profile sheet roofing over staircase mumty room at FM, AV, DDK Campus, Chennai.				

The conditions and quotation schedule will be issued from **06.10.2025** to **15.10.2025** on all working days between **10.00AM** to **3.00PM** on written requisition from the eligible contractors on production of:

1. Proof of valid Registration
2. Latest GST Return (**AUGUST 2025**)

The Quotations will be received by the undersigned up to **03.30 PM** on **15.10.2025** and will be opened by him at Civil Construction Wing, All India Radio, Chennai - 15 on the same day at **04.00 pm**. The quotation should be addressed to "The Assistant Engineer(C), Civil Construction Wing, All India Radio, Chennai-15.

The acceptance of the Quotations will rest with the undersigned who does not bind himself to accept the lowest quotations received without assigning any reason.

Unconditional rebate, if any has to be mentioned in the financial bid document itself and any rebate letter received in a separate envelope will be ignored.

The condition and quotation schedule shall be obtained and submitted to The Assistant Engineer(C), CCW, AIR, Chennai-15, before the stipulated date and time. The NIQ, schedule uploaded in the Tender wizard is only for the purpose of wide publicity and view only. **Schedule shall not be uploaded by the eligible contractors for submission of quotation in the (<https://prasarbharati.eproc.in>).**

CONDITIONS:

1. Work should be completed within 15 Days from the date of issue of order.
2. The work should be carried out as per the directions of the Engineer-in-Charge.
3. The cess at the rate of 1 %(one percent) would be deducted from the total cost as per works welfare cess Act 1996.
4. GST will be deducted as per statutory laws.

The Quotation notice may also be seen at website (<https://prasarbharati.eproc.in>)

- /SD/-

ASSISTANT ENGINEER (CIVIL)
FOR AND BEHALF OF THE PRESIDENT OF INDIA.

ABSTRACT						
Name of the work: Providing GI profile sheet roofing over staircase mumty room at FM, AV, DDK Campus, Chennai.						
Sl.No	Description	Qty		Rate	Unit	Amount
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in superstructure above plinth level up to floor V level in all shapes and sizes in :					
	a) Cement mortar 1:6(1 cement : 6 coarse sand)	0.30	cum		cum	0.00
2	15 mm cement plaster on the rough side of single or half brick wall of mix:					
	a) 1:6 (1 cement: 6 fine sand)	3.50	sqm		sqm	0.00
3	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	33.00	sqm		sqm	0.00

4	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. Note: - This item to be used for maintenance work judiciously, necessary deduction for scaffolding in the existing item to be done.	66.00	sqm		sqm	0.00
						0.00