


2 Scope of Work:: Packaged (15*4)Ton AC Plant Maintenance repairing , replacement and other associated works at DDK Gwalior. associated work as follows (5 ton*3)in one unit , total 4 units

- I. Servicing of 4 package units and descaling of 15*4 ton central AC plant.
- II. checking of Electric wiring , Relay , contactor , tag block and defective are replaced.
- III. Checking of compressor cooling and Top up of gas. Repair the defectives/replace
- IV. Overhauling of 2 nos.10HP 3 phase motor
- V. replacement of two nos . girderbase for motor (size W*L*H=1.5feet*9inch*4inch).
- VI. Replacement of 5 inch 60 feet inlet and outlet iron pipe of cooling Tower.preparation of cooling towergirder base(size 8*5feet*4 inch),
- VII. cooling tower water tank base of PVC 4 mm floor replace (size 6*5*1 feet)
- VIII. preparation of Two Nos .base of water tank RCC (size 5feet*6.5feet*2.5 inch).
- IX. Replacement of Honey comb pad of cooling tower (size 6.5*5.5*5feet) two Nos.
- VIII . Replacement of iron valve ,4 nos 5 inch gate valve, 2 nos.2 inch drain valve and 1inch valve 2 nos
- IX All rates should be with fitting charges.

3 Rate schedule/Price Bid:

| Sr No | Description of work | Quantity | Rate | GST | HSN/SAC code | Amount |
|-------|--|-------------|------|-----|--------------|--------|
| 1 | Servicing of 4 package units and descaling of 15*4 ton central AC plant | 1 job | | | | |
| 2 | checking of Electric wiring , Relay , contactor , tag block and defective are replaced | 1 job | | | | |
| 3 | Checking of compressor cooling | 1 job | | | | |
| 4 | Gas top up for compressor @KG | As required | | | | |
| 5 | Overhauling of 2 nos.10HP3 phase motor greasing | 1 job | | | | |
| 6 | Replacement of two nos. girder base for 10HP 3 phase motor (sizeW*L*H=1.5feet *9inch*4inch). | 1 job | | | | |
| 7 | Replacement of 5 inch 60 feet inlet and outlet iron pipe of cooling Tower. With fitting | 1 job | | | | |
| 8 | Preparation of cooling tower Girder base(size 8ft*5ft*4inch), | 1 Job | | | | |
| 9 | cooling tower watertank base floor PVC 4mm replace (size 6*5*1 feet) | | | | | |
| 10 | Preparation of Two Nos .base of water tankRCC 2.5 inch(size 5ft*6.5ft*2.5inch). | 1 job | | | | |
| 11 | Honey comb pad of cooling tower two nos(size 6.5*5.5*5ft). With installation | 1job | | | | |
| 12 | Iron gate valve 5-inch gate valve, 04 2-inch drain valve, 02 1inch valve 02 With fitting | 1job | | | | |


 04/11/25
 प्रमाणित निदेशक (अभि)
 इंदूर जिला न्यायालय