

PRASAR BHARATI
(India's Public Service Broadcaster)
Office of The Assistant Engineer (E)
Civil Construction Wing: All India Radio
#7, Kamarajar Salai, AIR Campus, Chennai-600004
Email: - aeccwchennai@gmail.com, Phone: 044-29997289/189

No. AE(E)/CHN/W-1/2025-26/

Dated: 26.02.2026

NOTICE INVITING e-QUOTATION

The Assistant Engineer (Elect), Civil Construction Wing, All India Radio, Chennai-04 on behalf of President of India invites item rate quotation from the approved and eligible Contractors of CPWD and those of appropriate list of M.E.S, BSNL Railway, Department of Post and State Government of Tamilnadu dealing with buildings for the following work:

Name of work:	Routine Minor Works of the year – 2025-26 for Civil Circle Office, CCW, AV, Chennai-05 (SH: Providing service connection cable).
NIQ No:	02/AE(E)/CCW/AIR/CH/2025-26/ Dated. 26.02.2026
Estimated Cost:	Rs. 89,117/-
Period of completion:	30 (Thirty) Days
e-tender processing fee	Nil
Last date for submission of bid	06.03.2026 up to 2.00 pm
Date of opening of Bids	06.03.2026 at 2.30 pm

The blank quotation duly signed by Assistant Engineer(E) shall be issued to agency on submission of application and submit to this office on or before the last date for submission of bids. Bids received late or received without the documents specified below will be summarily rejected.

List of documents to be submitted along with the quotation

- 1.Enlistment order of the Contractor and Electrical license.
- 2.The certificate of registration of GST.(The agencies who are not registered with department for GST shall be liable for rejection of tender.)
- 3.The successful bidder shall submit the acknowledgement of GST returns for December 2025 within a week's time of opening date of quotation.

The bid forms and other details can be obtained from the web site

<https://prasarbharati.eproc.in>.

Terms and conditions

1. The work should be completed as per CPWD specifications with upto date correction slips and as per the direction of Engineer-in-charge
2. No T&P will be issued departmentally.
3. The Quotations received without sealed cover and incomplete shape shall be summarily rejected.
4. The rates should be Net & inclusive of GST and levies.
5. The rates should be valid for one month from the date of opening.
6. No advance payment shall be made.
7. The work shall be completed within 30 Days.


ASSISTANT ENGINEER(ELECT.)
CCW,AIR,CHENNAI

Copy to:

1. The SE(C), CCW, Akashvani, Chennai-05 for kind information.
2. The Executive Engineer (E), CCW, AIR, Chennai-04.
3. Web updates pbns@gmail.com for publishing in AIR web site.
4. Notice board.


ASSISTANT ENGINEER(ELECT.)
CCW,AIR,CHENNAI



PRASAR BHARATI
(INDIA'S PUBLIC SERVICE BROADCASTER)
ASSISTANT ENGINEER (ELECTRICAL)
ELECTRICAL WING:AKASHVANI: CHENNAI -04.

Tender number: NIQ.No.02/AE/E/CCW/AIR/CHN/2025-26

Name of Work: Routine Minor Works of the year – 2025-26 for Civil Circle Office, CCW, AV, Chennai-05
(SH: Providing service connection cable).

NAME OF THE CONTRACTOR						
Sl.No	DESCRIPTION OF ITEM	QUANTITY		RATE (Rs)	UNIT	AMOUNT (Rs)
1	Supplying and laying PVC insulated PVC sheathed/XLPE aluminium conductor armoured UG cable of 1.1KV grade of size 3 1/2 x 35 Sq.mm confirming to IS 7098 part I 1988 with upto date amendment and laying the same as follows:					
	a)Through existing GI/PVC/RCC/HUME /DWC pipe as required	50	meters		metre	-
	b) Through existing masonry open duct/for connection/ looping etc. as required.	5	meters		metre	-
2	Providing and fixing 6 SWG dia GI wire on surface or in recess for loop earthing alongwith existing surface/recessed conduit/submain wiring/cable etc.as required.	110	meters		metre	
3	Supplying and making end termination with brass compression gland and aluminium lugs suitable for following size of PVC insulated PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required.					-
	a) 3 1/2 x 35 sqmm(32 mm)	2	Sets		set	
4	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. confirming to IS 14930, part II complete with fittings and cutting , jointing etc direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc complete as required.					-
	a) 63 mm dia (OD 63 mm & ID -51 mm nominal)	25	Mtr		each	
5	Supplying and fixing 50mm dia "B" class GI pipe including bends, mettalic clamps etc. as follows;					-
	a) On surface/wall for cable entry as required. (TATA/JINDAL make)	17	Mtr		Mtr	
	b) Direct in ground including excavation and refilling the trench etc. as required. (TATA/JINDAL make)	7	Mtr		Mtr	-

6	Cutting of existing concrete/bituminous road for laying earth strip/pipe or for earthing pit etc and making good the same with 1:2:4 cement concrete as required.	0.5	Cu M		Cu M	-
7	Dismantling and re-laying of of existing interlocking tiles on road and making good the same etc complete as required.(0.3 M width)	20	mtr		Mtr	-
TOTAL						-

CONTRACTOR


 ASSISTANT ENGINEER(E)
 ASSISTANT ENGINEER (ELECTRICAL)
 CIVIL CONSTRUCTION WING
 ALL INDIA RADIO
 CHENNAI