PRASAR BHARATI
(INDIA's PUBLIC SERVICE BROADCASTER)
AKASHVANI :: KOHIMA
PB.NO.42.PIN-797001. T/F-0370 2245556
kohima@prasarbharati.gov.in/kohimaair@gmail.com

No.Koh. 10 (2)/MW-1/2024-25/E 531 Date: 01/09/2026

Sub: Dismantling, Shifting and Re-installation of 100W FM Mast at Akashvani CRS Tuensang.

RATES SHOULD BE QUOTED ALSO IN FIRMS' LETER HEAD IN THE FOLLOWING PROFORMA

Last date of receiving of quotation in the office of the Assistant Director, AD(E), AKASHVANI KOHIMA, OLD MINISTERIAL HILL, KOHIMA -797001 **time:- 12 hrs on 14/09/26**

Sl.no	Description of work	qty	Rate	Amount
1	Dismantling of 30m guy mast with 10 no's section and with 2 no's dipole FM antenna, power divider branch cable, 7/8" RF cable 70m length with all accessories.	1		
2	Shifting of all tower material as per list from DC office (LPTV site) to NAP camp approx.. 8km. NAP campus is approx... 100m head load shifting upstairs from main road.	1		
3	Construction of 30m tower as per drawing including guy anchor, foundation bolt, bulldog grip D shackle, 10mm steel rope, turn buckle, etc. providing of damage material.	1		
4	Construction of 03 No's copper earthling as per drawing 1 for RF cable, 1 for lightning arrester and 1 for audio cable providing 10*25 mm copper strip.Paymennt will be done as per measurement.	1		
5	Supply fixing of copper lighting arrester, length 1m 10mm dia including 10mm copper wire Havel's make both end copper lug approx.. 35m.	1		
6	Supply fixing of solar mast light of medium intensity with sensor (Getronics make).	1		
7	Painting of 30m guy mast as per civil aviation norms with all guy anchor end greasing and pre-wrapping must be there.	1		

N.B. :(1) The tenderer should submit the experience certificate of same type of work.Firm's may visit the sites before quoting the rates. No correspondence / clarification will be made with any of the tender after submission of the bid offer.

(2) Please note that the work may involve additional one or couple of climbing of the professional mast workers in order to set the antenna system to the satisfaction of the AIR representative. The final measurement of entire RF chain (RF cable, Rigid line, RF Switch etc.) will be carried out by AIR representative with suitable measuring equipment. Entire system will also be tested on power, before release of completion certificate.

WITHOUT THE FOLLOWING DETAILS OFFER WILL BE REJECTED

1. Only after site visit submit the quotation and inform to Akashvani Kohima by mail (kohimair@gmail.com)
2. Copy of labor insurance must be submitted along with quotation.
3. GST Details, PAN, Trade License copy must be submitted along with quotation.
4. No accommodation will be provided inside Akashvani campus during the work.
5. Firm has to visit the site within 10days from the date of tender.
6. **Firm Registration Certificate, PAN, VAT, Service tax, GST Certificate should be submitted along with quotation.**
7. **Validity :** Six months from the opening date of bid.
8. Tenderer shall quote price for each item separately with necessary break details.
9. **Warranty:** warranty period of 1(one) year from the date of completion.
10. Rate should be quoted in the above annexure or in Firm's letter head in the same format of annexure otherwise quotation will be rejected.
11. **Consignee: Akashvani Kohima, Nagaland**
12. NO ADVANCE PAYMENT IS ADMISSIBLE.
13. QUOTATION SHOULD STRICTLY COMPLY WITH THE ATTACHED TERM & CONDITIONS.
14. DETAILS OF CATALOGUE, PRICE LISTS OF THE ITEMS SHOULD BE ENCLOSED WHERE EVER APPLICABLE.
15. TERMS OF DELIVERY AT OFFICE GODOWN/CONSIGNEE SHOULD BE CLEARLY INDICATED.
16. PLACE OF DELIVERY OTHER THAN GODOWN WILL BE CLEARLY MENTIONED IN QUOTATION
17. IN CASE OF CONTRACT WORK, WHETHER THE FIRM HAS OBTAINED LICENCE UNDER CONTRACT LABOUR ACT, IF YES, GIVE THE LICENCE NUMBER.

1.9.26

SIGNATURE OF TENDERER

TENDERER'S FULL ADDRESS
AKASHVANI :: KOHIM
PB.NO.42.PIN-797001. T/F-0370 2245556

Assistant Engineer
सहायक अभियंता
All India Radio Kohima
आकाशवाणी कोहिमा