



प्रसार भारती PRASAR BHARATI
(भारत का लोकसेवा प्रसारक INDIA'S PUBLIC SERVICE BROADCASTER)
अपरमहानिदेशक (प्रसारण संचालन) (पूर्वोत्तर क्षेत्र) का कार्यालय
OFFICE OF THE ADDITIONAL DIRECTOR GENERAL (BO) (NEZ)
आकाशवाणी एवं दूरदर्शन AKASHVANI AND DOORDARSHAN
दूरदर्शन संकुल, आर.जी.बरुआ मार्ग, गुवाहाटी - 781 024
DOORDARSHAN COMPLEX, R.G.BARUAH ROAD, GUWAHATI - 781 024



No. ADG(E)(NEZ)/Projects/AIR_LONGTHARAI/2026-27-Part(1)

Date: 12.10.2026

NOTICE INVITING QUOTATION

Subject: - Request for Budgetary Rate Quotation for floor tiling works in Transmitter Hall at Akashvani Longtharai (Tripura) under O/o ADG (A & BO) (NEZ), Akashvani & Doordarshan, Guwahati – regarding.


Sir,

Budgetary Quotation is invited from reputed and experienced firms/ contractors for the proposed floor tiling works in the Transmitter Hall of Akashvani Longtharai, for the purpose of preparation of estimate. The details of work and terms are as under:

1. Name of Work: Improvement of floor by providing vitrified tile flooring in Transmitter Hall at Akashvani Longtharai (Tripura).
2. Location: Transmitter Hall, Akashvani Longtharai (Tripura).
3. Approximate Area: 24 ft x 17 ft = 408 Sq. ft
4. Scope of Work / Schedule of Items: You are requested to quote your best rates for the following items. The rates should be inclusive of all materials, labour, transportation to site, loading/unloading, T&P, wastage and all taxes/GST.

Sl. No.	Description of Item	Qty.	Rate Per Unit (Rs.)	Amount (Rs.)
1	Removal and disposal of existing PVC carpet from floor	408 Sq. ft.		
2	Chipping/removal of the existing concrete floor to a depth of at least 50 mm, as required, so that the finished floor level after laying of tiles remains the same as the existing floor level.	408 Sq. ft.		
3	Providing and laying ISI-marked, IS 15622-compliant, 2 ft. x 2 ft. x 10 mm thick double-charged vitrified tiles (glossy finish), including necessary bedding, fixing, jointing and finishing.	408 Sq. ft.		
4	Covering the existing cable trenches with suitable wooden covers, duly topped with 3 mm thick PVC flooring, ensuring proper alignment and finished appearance.	As per actual (Sq. ft.)		
5	Carrying out all other incidental/associated works required for proper completion and giving the floor a neat and finished appearance.	1 Lump sum		

Yours faithfully


Rakesh Gupta

Senior Engineering Assistant

For O/o ADG (A & BO) (NEZ), Akashvani & Doordarshan,
Guwahati.