प्रसारभारती PRASAR BHARATI
(भारत का लोकसेवा प्रसारक INDIA's PUBLIC SERVICE BROADCASTER)
कार्यालय अपर महानिदेशक (प्रसारण संचालन) (पूर्वोत्तरक्षेत्र)
OFFICE OF THE ADDITIONAL DIRECTOR GENERAL (A & BO) (NEZ)
आकाशवाणी एवं दूरदर्शन AKASHVANI AND DOORDARSHAN
दूरदर्शन परिसर, आर.जी.बरुआ मार्ग, गुवाहाटी- 781 024
DOORDARSHAN COMPLEX, R.G.B.ROAD, GUWAHATI - 781024
सत्यम् शिवम् सुन्दरम्

File No.: ADG (E) (NEZ)/Projects/AIR Diphu/2026-27-Part (4) **Date: 17/11/2026**

NOTICE INVITING QUOTATION

Subject: Repairing and Re-painting of inside transmitter hall back side wall, Transmitter hall cable trench length increase, Supply of changeover switch, minor repairing and Re-painting of DG Room - 02 Nos. at Akashvani Diphu (Assam).

Dear Sir,

This office is interested in the under mentioned works as per the specifications given below. Your quotation is invited as per the terms and conditions given below:

Sl. No.	Description of Work	Qty.
1	**Inside Transmitter Hall — Back Side Wall:** i. Inside transmitter hall backside wall existing window type AC **3 nos**. wall hole has to be blocked with a brick wall and smooth plastering both side of the wall. ii. Painting work has to be done after the wall repairing works are completed. Application of one coat Wall Putty work, one coat Wall Primer and application of two coats of Acrylic Wall Emulsion Paints and matching with existing another wall colour etc. **(Size of wall — 16½ ft. x 10 ft.).** iii. Increase Transmitter Hall Cable Trench length and replacement of old wooden trench cover with supply of new trench cover along with **2 mm** thick PVC Flooring Sheet for trench cover **(Currently Cable Trench length = 11 ft. long x 14 inch wide and total required length 14 ft. x 14 inch**).	**1 Job**
2	**SITC of One 100 Amp. Changeover Switch:** Supply, Installation, Testing & Commissioning (SITC) of **one no. of 100 Amp**. Changeover Switch, make — Havells or similar, wall mounting — one job.	**As per requirement**
3	**DG Room No. 1— Minor Repairing** Minor repairing of DG Room inside wall and ceiling which is damaged by roof leakage and repairing of roof leakage area by use of Asian Paints Damp Proof Xtreme Salt Shield etc. After completion of the repairing works, application of one coat Wall Primer and two coats of Acrylic Emulsion Paints. (Size of DG Room inside — **30 ft. long x 17 ft. wide x 15 ft. height**). Including Supply of **02 Nos**. Tube light, ceiling fan and New electric wiring and required Switch Board.	**1 Job**
4	**DG Room No. 2 — Complete Cleaning & Repairing:** Complete cleaning the wild growth from rooftop of the DG Room No. 2, minor repairing of DG Room inside wall and ceiling which is damaged by roof leakage. And after repairing application of one or more coat — Asian Paints Damp Proof Xtreme Salt Shield and application of one coat Wall Primer and 2 coats of Acrylic Wall Emulsion Paint. **(Size of DG Room inside — 22 ft. long x 10 ft. wide & Rooftop size approx. — 22 ft. x 14 ft.)**	**1 Job**

Yours Faithfully

17/11/2026

Sudhakar Singh
Senior Engineering Assistant
For O/o ADG (A & BO) (NEZ), Akashvani and Doordarshan, Guwahati

Terms and conditions: -

1. The rates should be indicated in figure as well as in words.
2. The quotation should be sent to the undersigned by name along with the descriptions of works/ items, name of supplier/ Contractor and specification etc. as per requirement of this office. The terms and conditions, validity period etc. should separately be mentioned in cover envelop or ignore whichever is not necessary. The same must be sealed and containing quoted prices, GST etc. to be furnished in the quotation or in the quotation form enclosed herewith so as to reach within 12.00 hours on or before 30/11/2026 in sealed cover, quotations by giving the following details.
    a. Works/ stores/ items for which quotations are enclosed.
    b. Reference of enquiry letter.
    c. Date of opening quotations.
    d. Name and address of the Tenderer.
    e. Details of quotation should be submitted in the enclosed form or firm's quotation form.
3. The quotations will be opened in the Office of the undersigned at 3.00 p.m. on 30/11/2026 in the presence of the tenderer or their agents who may choose to attend.
4. The quotations as submitted should remain open for acceptance for a period of 6 months from the date of opening.
5. Every care has to be taken for the safety of the operating/ carrying the above- mentioned works/ stores/ items at the risk of Supplier/ Contractor.
6. The quotation should be fulfilled with the requisite particulars for GST implication.
7. The O/o ADG (BO) NEZ, Guwahati reserves the right to reject any or all the quotations without assigning any reasons.
8. The quality of work should be guaranteed for 1 (one) year after completion.
9. This office reserves the right to terminate the contract if the workmanship is found unsatisfactory. The decision of Head of Engineering in the matter will be final and undisputable. Income Tax will be deducted from firm's bill at the prescribed rates and the prescribed certificate for TDS will be issued.

Copy to:

1) webupdates.pbns@gmail.com with a request to publish the Notice inviting quotation on prasarbharati.gov.in
2) O/o ADG (A & BO) NEZ, Guwahati office Notice Board.