प्रसारभारती PRASAR BHARATI
(भारत का लोकसेवा प्रसारक INDIA's PUBLIC SERVICE BROADCASTER)
कार्यालय अपर महानिदेशक (प्रसारण संचालन) (पूर्वोत्तरक्षेत्र)
OFFICE OF THE ADDITIONAL DIRECTOR GENERAL (A & BO) (NEZ)
आकाशवाणी एवं दूरदर्शन AKASHVANI AND DOORDARSHAN
दूरदर्शन परिसर, आर.जी.बरुआ मार्ग, गुवाहाटी- 781 024
DOORDARSHAN COMPLEX, R.G.B.ROAD, GUWAHATI - 781024

सत्यम् शिवम् सुन्दरम्

File No.: ADG (E)(NEZ)/Projects/ AIR_Tura/2026-27-Part(3) **Date: 17/11/2026**

NOTICE INVITING QUOTATION

Subject: Minor repairing of Transmitter Hall inside — wall crack repairing, replacement of false ceiling damaged tiles, painting of TR. Hall and providing one Aluminium partition inside the TR Hall Glass Cabin etc. at Akashvani Tura (Meghalaya).

Dear Sir,

This office is interested in the under mentioned works as per the specifications given below. Your quotation is invited as per the terms and conditions given below:

Sl. No.	Description of Work	Qty.
1	Repairing & replacement of existing false ceiling damaged tiles wherever necessary. Replacement of total tiles approx. **15 Nos. Size – 2 ft. x 2 ft.**	**01 Job**
2	Repairing of false ceiling and replacement of damaged tiles and painting. Application of one coat wooden primer and two coats of synthetic enamel paint colour – White, Supply of paints – Asian, Berger, Dulex etc. ***Total area of False Ceiling = 31 ft. Long and 21 ft. Wide.**	**01 Job**
3	Minor repairing and re-fixing of Aluminium Door for TR. Hall entry door.	**01 Job**
4	Minor repairing and re-fixing of Aluminium Door for TR. Hall entry door.	**01 Job**
5	Painting of Transmitter Hall inside after completion of wall crack repairing works. Complete scrapping and cleaning of old paints of the existing wall and after application of one coat wall putty, one coat wall primer and two coats Acrylic wall emulsion paints etc. Supply of paints make–Berger, Asian and similar, etc. ***Total wall area: Length– 31 ft. x Width– 21 ft. x Height– 11 ft.**	**01 Job**
6	**Supply, Fabrication and Installation of Aluminium Partition:** Supply, Fabrication and Installation of one Aluminium Partition inside the FM TR. Hall Glass Cabin for separate partition of LT Panel with FM TR. Racks etc. *Partition area – **12 ft. Long x 11 ft. Height = 132 Sq. ft.** (Total area) *Supply of Aluminium items – **1.5 mm** thick and Glass – **5 mm** thick	**As per requirement**

Yours Faithfully

17/11/2026

Sudhakar Singh
Senior Engineering Assistant
For O/o ADG (A & BO) (NEZ), Akashvani and Doordarshan,
Guwahati.

Terms and conditions: -

1. The rates should be indicated in figure as well as in words.
2. The quotation should be sent to the undersigned by name along with the descriptions of works/ items, name of supplier/ Contractor and specification etc. as per requirement of this office. The terms and conditions, validity period etc. should separately be mentioned in cover envelop or ignore whichever is not necessary. The same must be sealed and containing quoted prices, GST etc. to be furnished in the quotation or in the quotation form enclosed herewith so as to reach within 12.00 hours on or before 30/11/2026 in sealed cover, quotations by giving the following details.
    a. Works/ stores/ items for which quotations are enclosed.
    b. Reference of enquiry letter.
    c. Date of opening quotations.
    d. Name and address of the Tenderer.
    e. Details of quotation should be submitted in the enclosed form or firm's quotation form.
3. The quotations will be opened in the Office of the undersigned at 3.00 p.m. on 30/11/2026 in the presence of the tenderer or their agents who may choose to attend.
4. The quotations as submitted should remain open for acceptance for a period of 6 months from the date of opening.
5. Every care has to be taken for the safety of the operating/ carrying the above- mentioned works/ stores/ items at the risk of Supplier/ Contractor.
6. The quotation should be fulfilled with the requisite particulars for GST implication.
7. The O/o ADG (BO) NEZ, Guwahati reserves the right to reject any or all the quotations without assigning any reasons.
8. The quality of work should be guaranteed for 1 (one) year after completion.
9. This office reserves the right to terminate the contract if the workmanship is found unsatisfactory. The decision of Head of Engineering in the matter will be final and undisputable. Income Tax will be deducted from firm's bill at the prescribed rates and the prescribed certificate for TDS will be issued.

Copy to:

1) webupdates.pbns@gmail.com with a request to publish the Notice inviting quotation on prasarbharati.gov.in
2) O/o ADG (A & BO) NEZ, Guwahati office Notice Board.