PRASAR BHARATI
(INDIA's PUBLIC SERVICE BROADCASTER)
AKASHVANI :: KOHIMA
PB.NO.42.PIN-797001. T/F-0370 2245556
kohima@prasarbharati.gov.in/kohimaair@gmail.com

No.Koh. 13(16)/2026-27/E 685 Date: 03/11/2026

Sub: Internal repairs inside Studio Building at CRS Tuensang.

RATES SHOULD BE QUOTED ALSO IN FIRMS' LETER HEAD IN THE FOLLOWING PROFORMA

Last date of receiving of quotation in the office of the Assistant Director, AD(E), AKASHVANI KOHIMA, OLD MINISTERS HILL, KOHIMA -797001 **time:- 12 hrs on 13/11/26**

Sl.no	Description of work	Qty	Rate	Amount
1	Providing and laying flooring, including preparation and levelling of the existing floor surface, necessary repairs, application of suitable adhesive/mortar, and providing and fixing approved quality flooring material, including cutting, fitting, jointing, grouting, skirting where required, finishing and cleaning, complete in all respects. Location: Inside Studio Building Area: 200 Sq. Ft	200 sq.ft		
2	Providing and fixing cotton curtains, including supply of approved quality cotton curtain fabric, stitching, hemming, and finishing to required size, complete with providing and fixing curtain hanging arrangement, curtain rods/pipes, wall-mounted brackets, supports, hooks/rings and all necessary hardware and accessories, complete in all respects. Location: Studio Room Curtain Height: 9ft Curtain Length: 55ft (Total)	495 Sq. ft		
3	Providing and laying 0.5 mm thick PVC flooring in the Studio including preparation, cleaning, application of approved suitable adhesive, cutting and fitting of PVC sheerstites, proper jointing, and finishing, incluting and necessary materials, labour, and accessories, complete in all respects. Location: Studio Room Floor Dimension: 20ft x 20ft	400 Sq.ft		
4	Providing and fixing an observation window, including fabrication and installation of the required frame, provision and fixing of 6mm thick clear glass,			

	complete with all necessary hardware fittings, beading, sealant, fasteners, hinges/handles, and other accessories, including cutting, fitting, alignment, and finishing, complete in all respects Location: Studio Room Opening Dimension: 2ft x 3ft	1 Job		
5	Repairing existing damaged ceiling, including scraping and removal of loose/damaged portions, cleaning, and preparation of the surface, providing, and fixing necessary wooden support framework, and providing and fixing new ceiling boards of approved quality, including cutting, fitting, jointing, screws, finishing and all necessary accessories, complete in all respects. Location: Inside Studio Building Ceiling Dimension: 30 Nos of 2ft x 2ft Panels	120 Sq. Ft		
6	Repairing existing damaged walls of the Control Room, including scraping and removal of loose/damaged portions, cleaning, and preparation of the surface, providing, and fixing necessary support members and framework, and providing and fixing approved quality wall boards/panels, including cutting, fitting, Jointing, screws, finishing and all necessary accessories, complete in all respects. Location: Internal Wall Control Room inside studio Building Wall Dimension: 15ft x Sft	120 Sq. ft		

N.B. :(1) The tenderer should submit the experience certificate of same type of work.Firm's may visit the sites before quoting the rates. No correspondence / clarification will be made with any of the tender after submission of the bid offer.

SIGNATURE& SEAL OF TENDERER

11/2026

डी. अदाफ्रो
D. Adaphro
सहायक निदेशक (अभियान्त्रिकी)
Asstt. Director (Engg.)
आकाशवाणी, कोहिमा
Akashvani, Kohima

WITHOUT THE FOLLOWING DETAILS OFFER WILL BE REJECTED

1. Only after site visit submit the quotation and inform to Akashvani Kohima by mail (kohimair@gmail.com)
2. Copy of labor insurance must be submitted along with quotation.
3. GST Details, PAN, Trade License copy must be submitted along with quotation.
4. No accommodation will be provided inside Akashvani campus during the work.
5. Firm has to visit the site within 10days from the date of tender.
6. **Firm Registration Certificate, PAN, VAT, Service tax, GST Certificate should be submitted along with quotation.**
7. **Validity :** Six months from the opening date of bid.
8. Tenderer shall quote price for each item separately with necessary break details.
9. **Warranty:** warranty period of 1(one) year from the date of completion.
10. Rate should be quoted in the above annexure or in Firm's letter head in the same format of annexure otherwise quotation will be rejected.
11. **Consignee: Akashvani Kohima, Nagaland**
12. NO ADVANCE PAYMENT IS ADMISSIBLE.
13. QUOTATION SHOULD STRICTLY COMPLY WITH THE ATTACHED TERM & CONDITIONS.
14. DETAILS OF CATALOGUE, PRICE LISTS OF THE ITEMS SHOULD BE ENCLOSED WHERE EVER APPLICABLE.
15. TERMS OF DELIVERY AT OFFICE GODOWN/CONSIGNEE SHOULD BE CLEARLY INDICATED.
16. PLACE OF DELIVERY OTHER THAN GODOWN WILL BE CLEARLY MENTIONED IN QUOTATION.
17. IN CASE OF CONTRACT WORK, WHETHER THE FIRM HAS OBTAINED LICENCE UNDER CONTRACT LABOUR ACT, IF YES, GIVE THE LICENCE NUMBER.

TENDERER'S FULL ADDRESS
AKASHVANI :: KOHIMA
PB.NO.42.PIN-797001. T/F-0370 2245556

SIGNATURE OF TENDERER
03/11/2026

डी. अदाफ्रो
D. Adaphro
सहायक निदेशक (अभियान्त्रिकी)
Asstt. Director (Engg.)
आकाशवाणी, कोहिमा
Akashvani, Kohima