PRASAR BHARATI
(INDIA'S PUBLIC SERVICE BROADCASTER)
OFFICE OF THE EXECUTIVE ENGINEER (ELECT)
CIVIL CONSTRUCTION WING : AKASHVANI
#7, KAMARAJAR SALAI, AIR CAMPUS
CHENNAI – 600004
✉:eeechennai@gmail.com ✆: 044-29997289

No: 02/EE(E)/CCW/AIR/CHN/2026-27/349

Dt. 18/11/2026

SHORT NOTICE INVITING QUOTATION

The Sealed item rate quotations are hereby invited by the Executive Engineer (Elect.), CCW: AV: Chennai on behalf of the PRESIDENT OF INDIA from the approved and eligible contractors of CPWD and those who are on working/ appropriate list of BSNL, MES, Railways, Department of Post and Kerala State PWD for the following work.

The quotations will be received up to **11.00** Hrs. on **24/11/2026** and shall be opened on **24/11/2026** at **11.30** Hrs. The quotations should be addressed to the Executive Engineer(Elect.), CCW, Akashvani, Chennai superscribing the envelope with 'Name of work' as below

The Acceptance of quotation will rest with the undersigned who does not bind himself to accept the lowest quotation and reserves the right of rejecting any or all quotations received without assigning any reason.

Name of work: **Replacement of 11 KV indoor CT-PT in the existing HT Metering unit at Akashvani, Calicut.**

Sl. No.	Description of Item	Quantity	Rate	Unit	Amount
	As per sheet attached				
				Total	

Conditions:

1. No advance payment will be given.
2. The quoted rates shall be inclusive of all charges, taxes, duties and other incidental expenses. No additional payment shall be admissible on any account whatsoever.
3. The time limit for the work is 01 (One) Month.
4. Specification: CPWD General Specifications for Electrical Works 2023 (Part I & II) and Part IV - Substation - 2013 with up-to-date amendments.
5. The contractor shall possess a valid HT Contractor's Licence issued by the Kerala State Electricity Licensing Board.
6. The agency has to submit copy of GST registration certificate along with quotation.

18/11/26

Executive Engineer (E)
CCW: AV: Chennai

Copy to:

1. PBNS Team (webupdates.pbns@gmail.com) with a request to publish in the PrasarBharati website (E mail)
2. The Superintending Engineer (E), CCW, AV, Nagpur (by Email)
3. The Deputy Director (E), AV, Calicut for favour of information (by Email).
4. The Assistant Engineer (Elect), CCW, AV, Calicut for information (by E mail).
5. Notice Board.

18/4/26

Executive Engineer (E)

SCHEDULE

Name of work : Replacement of 11 KV indoor CT-PT in the existing HT Metering unit at Akashvani, Calicut.

Sl. No	Description of item	Quantity		Rate	Unit	Amount
1	Supplying, installing, testing and commissioning of 11 KV, resin cast/ indoor type, 3 Nos CTs of 10/5A current ratio, 10 VA burden, accuracy class 0.2S and one no. resin cast/ indoor type PT of 11KV/110V votage ratio, burden 25 VA, accuracy class 0.2 as per KSEBL specifications (BIS), to be installed in the existing INTRANS BRAND 11 KV OUTDOOR LOAD BREAK SWITCH METERING PANEL including connections from CT PT to existing test terminal block (TTB) by means of 12 core x 2.5 sq.mm unarmoured copper control cable, providing connection from TTB to TOD meter by means of 4 sq.mm FRLS copper wire etc.in corordination with the KSEB authorities as required.**(Make: M/s. Intrans Electro Components/ Indus/ELpower)**	1	Set		Set	
2	Service charges for testing and calibration of CT-PT unit at KSEB's TMR Division Office at Dharmashala, Kannur and getting the test certificate including transportation charges, statuatory testing charges etc. complete as reuired.	1	Job		Job	
3	Supplying and fixing of 11 KV, 20 A, HRC fuses as per existing panel configeration etc. as required.	3	Nos		Each	
4	Carrying out insulation resistance tests on the HT Metering Panel, HT cables, HT Panel in the Studio Block, Transformers and other associated electrical equipment, etc. as required.	1	Job		Job	
					Total	

Contractor

Executive Engineer (Elect)