PRASAR BHARATI
(INDIA's PUBLIC SERVICE BROADCASTER)
AKASHVANI :: KOHIMA
PB.NO.42.PIN-797001. T/F-0370 2245556
kohima@prasarbharati.gov.in/kohimaair@gmail.com

No.Koh.10(2)/2026-27/E/1694 Date: 04/11/2026

Sub: Construction of cement concrete road to quarter MRH/AIR-12 at Merhulietsa Colony, Kohima, Nagaland.

RATES SHOULD BE QUOTED ALSO IN FIRMS' LETER HEAD IN THE FOLLOWING PROFORMA

Last date of receiving of quotation in the office of the Assistant Director, AD(E), AKASHVANI KOHIMA, OLD MINISTERS HILL, KOHIMA -797001 **time:- 12 hrs on 19/11/26**

Sl.no	Description of work	Qty	Rate	Amount
1	**Site Preparation & Earthwork** Clearing, dressing, excavation/filling, and preparation of formation to required lines, levels and profile, including disposal of surplus/unsuitable earth. **Formation & Compaction** Dressing, watering, and thorough compaction of the prepared subgrade, including treatment of soft or unstable patches with approved material. **Stone/Metal Soling** Providing, laying, hand-packing and compacting approved hard stone/metal soling to the required thickness, profile and gradient, including filling of voids with suitable spalls. **Concrete Casting** Providing, laying and compacting 120 mm (4") thick Cement Concrete over prepared soling, including mixing, placing, screeding and finishing to required levels and profile. **Formwork** Providing and fixing rigid, properly aligned timber/steel formwork to maintain the specified lines, levels, thickness and gradients during concrete works. **Control Joints** Providing properly aligned and suitably spaced contraction/control joints using timber/wooden formers to control shrinkage and cracking.	2100 sq.ft		

	Surface Finishing Screeding and finishing the concrete surface to the specified levels, cross-fall and gradient, free from significant undulations or depressions. **Drainage Gradient** Maintaining the specified longitudinal and transverse slope/cross-fall to ensure positive and unobstructed surface water drainage. **Curing & Protection** Proper curing and protection of completed concrete against premature drying, damage and loading during the required curing period. **Quality Control** Ensuring compliance with specified materials, thickness, levels, gradients, joint alignment, and workmanship; defective or nonconforming work shall be rectified by the contractor.			

N.B. : 1. The tenderer should submit the experience certificate of 3 years of same type of work. Firm's may visit the sites before quoting the rates. No correspondence / clarification will be made with any of the tender after submission of the bid offer.

2. Estimated amount for the work to be carried out should not be more than Rs.1,98,000/- (One Lakh Ninety Eight Thousand only).

05/11/26

SIGNATURE& SEAL OF TENDERER

डी. अदाफ्रो
D. Adaphro
सहायक निदेशक (अभियान्त्रिकी)
Asstt. Director (Engg.)
आकाशवाणी, कोहिमा
Akashvani, Kohima

WITHOUT THE FOLLOWING DETAILS OFFER WILL BE REJECTED

1. Only after site visit submit the quotation and inform to Akashvani Kohima by mail (kohimair@gmail.com)
2. Copy of labor insurance must be submitted along with quotation.
3. GST Details, PAN, Trade License copy must be submitted along with quotation.
4. No accommodation will be provided inside Akashvani campus during the work.
5. Firm has to visit the site within 10days from the date of tender.
6. **Firm Registration Certificate, PAN, VAT, Service tax, GST Certificate should be submitted along with quotation.**
7. **Validity:** Six months from the opening date of bid.
8. Tenderer shall quote price for each item separately with necessary break details.
9. **Warranty:** warranty period of 1(one) year from the date of completion.
10. Rate should be quoted in the above annexure or in Firm's letter head in the same format of annexure otherwise quotation will be rejected.
11. **Consignee: Akashvani Kohima, Nagaland**
12. NO ADVANCE PAYMENT IS ADMISSIBLE.
13. QUOTATION SHOULD STRICTLY COMPLY WITH THE ATTACHED TERM & CONDITIONS.
14. DETAILS OF CATALOGUE, PRICE LISTS OF THE ITEMS SHOULD BE ENCLOSED WHERE EVER APPLICABLE.
15. TERMS OF DELIVERY AT OFFICE GODOWN/CONSIGNEE SHOULD BE CLEARLY INDICATED.
16. PLACE OF DELIVERY OTHER THAN GODOWN WILL BE CLEARLY MENTIONED IN QUOTATION.
17. IN CASE OF CONTRACT WORK, WHETHER THE FIRM HAS OBTAINED LICENCE UNDER CONTRACT LABOUR ACT, IF YES, GIVE THE LICENCE NUMBER.
18. 3% SECURITY MONEY OF TOTAL CONTRACT VALUE WILL HAVE TO BE DEPOSITED BY THE FIRM ON BEING AWARDED THE WORK ORDER.

TENDERER'S FULL ADDRESS
AKASHVANI :: KOHIMA
PB.NO.42.PIN-797001. T/F-0370 2245556

SIGNATURE OF TENDERER
03/11/2020
डी. अदाफ्रो
D. Adaphro
सहायक निदेशक (अभियान्त्रिकी)
Asstt. Director (Engg.)
आकाशवाणी, कोहिमा
Akashvani, Kohima